


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Harvey	Township name Lake	Fraction CNE 1/4	Section number 22	Town number 24-S	Range number 3-W
Distance and direction from nearest town or city: Street address of well location if in city:			3 Owner of well: Edwin Regier Address: Burton, Kansas RR2 67020			
Locate with "X" in section below: N W E S 1 Mile			Sketch map: 			
2 Type and color of material			From	To	4 Well depth: 50 ft. Date of completion 5/20/75 Well diameter _____ in.	
Soil			0	2	5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
Clay			2	14	6 Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Commercial ☒ Test well ☐ _____	
Sand			14	45	7 Casing: Material: Galvanized Height: above/below Threaded ☐ Welded ☐ Surface 12 in. Diam. 16 in. to 24 ft. depth! Drive shoe? ☐ Yes ☒ No _____ in. to _____ ft. depth!	
Clay			45	50	8 Screen: Manufacturer Johnson Type Screen Dia. 16 Slot/gauze 3/16 Length 26 Set between 34 ft. and 50 ft. Fittings: Gravel pack ☒ Yes ☐ No Size range of material 1/8-1/4"	
					9 Static water level: 8 ft. below land surface Date 7/22/74	
					10 Pumping level below land surfaces: 40 ft. after 1 hrs. pumping 750 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 750 g.p.m.	
					11 Water sample submitted: ☐ Yes ☒ No Date _____	
					12 Well head completion: ☐ Pitless adapter ☒ _____ inches above grade	
					13 Well grouted? ☐ Yes ☒ No ☐ Neat cement ☒ Bentonite ☐ _____ Depth: From 0 ft. to 10 ft.	
					14 Nearest source of possible contamination: ft. _____ Direction _____ Type _____ Well disinfected upon completion? ☐ Yes ☒ No	
					15 Pump: ☐ Not installed Manufacturer's name Western Land Roller Model number 812CM HP 60 Volts 440 Length of drop pipe 40 ft. capacity 750 g.m.p. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
16 Remarks: elevation			17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Darling Drilling Co. 189 Business name _____ License No. _____ Address 1211 West 4th, Hutchinson, Ks Signed Darling Drilling Date 5/20/75 Authorized representative			