

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Harvey	Fraction SW 1/4 NE 1/4 SW 1/4	Section number 23	Township number T 24 S R 3 W E	Range number 3 W E
2. Distance and direction from nearest town or city: Street address of well location if in city:		1 mile East of Patterson 1/4 N 1/4 East in field		3. Owner of well: Les Valdois R.R. or street: Sedgwick, Kansas 67135 City, state, zip code:		
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: 		6. Bore hole dia. 28 in. Completion date 6-4-79 Well depth 52 ft. 6/4/79		
5. Type and color of material		From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
Top soil		0	3	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Brown clay		3	11	9. Casing: Material Transite Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☐ Weight 30 lbs./ft. Dia. 16 in. to 26 ft. depth Wall Thickness: inches or Dia. 16 in. to 26 ft. depth gage No. 346		
Med sand (red) tight formation		11	14	10. Screen: Manufacturer's name Johnson Type sawed Dia. 16 Net/gauze 3/16 Length 26 Set between 26 ft. and 32 ft. ft. and 32 ft. Gravel pack? yes Size range of material 1/8-1/4		
Clay		14	15	11. Static water level: 15 1/4 ft. below land surface Date 6/4/79 mo./day/yr.		
Med. red sand		15	17	12. Pumping level below land surfaces: 31 3/4 ft. after 1 hrs. pumping 900 g.p.m. 33 ft. after 2 hrs. pumping 950 g.p.m. Estimated maximum yield 950 g.p.m.		
Med. loose sand, took very little water		17	36	13. Water sample submitted: no. /day/yr. Yes ☒ No ☐ Date		
Med. sand w/green clay		36	38	14. Well head completion: ☐ Pitless adapter 12 inches above grade		
Med. sand		38	52	15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.		
Clay		52		16. Nearest source of possible contamination: ft. none Direction none Type none Well disinfected upon completion? ☐ Yes ☒ No		
(Use a second sheet if needed)				17. Pump: Not installed Manufacturer's name Western Land Roller Model number 45 Stage RCH 60 Volts 900 Length of drop pipe 540 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis Ent. Inc. 134 Business name License No. Address 1211 W. 4th Hutchinson, Ks. Signed Mike Flervo Date 7-27-79 Authorized representative		