

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Harvey	Fraction NW 1/4 SW 1/4 NE 1/4	Section number 25	Township number T 24 S	Range number R 3 E
2. Distance and direction from nearest town or city: Street address of well location if in city: 2 1/2 E. of Patterson				3. Owner of well: Tom Wendling R.R. or street: Halstead, Kansas City, state, zip code:		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: open field		6. Bore hole dia. 30 in. Completion date 4-15-77 Well depth 54 ft.		
5. Type and color of material		From		To		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary
		Topsoil		0	1	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
		Fine Sand		1	15	9. Casing: Material C-175b Height: Above or below Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☐ Weight 16 lbs./ft.
		Clay		15	20	Dia. 16 in. to 14 in. depth 14 ft. Wall Thickness: inches or Dia. 16 in. to 14 in. depth 14 ft. gauge No. 314
		Gravel - med		20	25	10. Screen: Manufacturer's name Johnson Type Cem-175b Dia. 30 16" Slot gauge 1/4 Length 13' Set between 41 ft. and 54 ft. Gravel pack? ☒ Size range of material 3/8
Clay		25	35	11. Static water level: 13 ft. below land surface Date 4/10/77		
Good Gravel		35	54	12. Pumping level below land surfaces: 20 ft. after 2 hrs. pumping 600 g.p.m. ft. after 2 hrs. pumping 600 g.p.m. Estimated maximum yield 700 g.p.m.		
				13. Water sample submitted: X Yes ☐ No Date		
				14. Well head completion: ☐ Pitless adapter 12 Inches above grade		
				15. Well grouted? ☒ X With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.		
				16. Nearest source of possible contamination: None ft. Direction Type Well disinfected upon completion? ☐ Yes ☒ No		
				17. Pump: Manufacturer's name Peerless Not installed Model number 7139 HP 30 Volts Length of drop pipe 40 ft. capacity 600 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weninger Irrigation 238 Business name Maize, Kans. License No. Address Ki Weninger Date 5-11 Signed Ki Weninger Authorized representative		