



USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Harvey	Fraction NE 1/4 NE 1/4 NE 1/4	Section number 26	Township number T 24	Range number S R 3	EW
2. Distance and direction from nearest town or city:		1 3/4 E of Patoka		Owner of well: Leslie Valdois			
Street address of well location if in city:		450		R.R. or street: R.R. 2			
				City, state, zip code: Sedgwick, Kansas 67135			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 26 in. Completion date 7/30/77 Well depth 108 ft.			
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary			
5. Type and color of material		From		To		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Med. sand		0		15		9. Casing: Material Transite Weight: Above or below Threaded ☐ Welded ☐ Surface ☒ 8 in. RMP ☐ PVC ☐ Weight 30 lbs./ft.	
Fine sand		15		20		Dia. 16 in. to 92 ft. depth Wall Thickness: inches or Dia. 16 in. to 92 ft. depth gage No. 92	
Med. gravel		20		25		10. Screen: Manufacturer's name Johnson Type sawed Dia. 16 Slot/gauze 3/16 Length 26 Set between 92 ft. and 108 ft. Gravel pack? yes Size range of material 1/8-1/4	
Good gravel		25		45		11. Static water level: 15 ft. below land surface Date 7/30/77 mo./day/yr.	
Fine sand		45		50		12. Pumping level below land surfaces: 37 ft. after 1 hrs. pumping 800 g.p.m. 30 ft. after 2 hrs. pumping 1000 g.p.m. Estimated maximum yield 1100 g.p.m.	
Sand and clay mixed		50		55		13. Water sample submitted: 1100 g.p.m. mo./day/yr. ☐ Yes ☒ No Date	
Fine sand w/ little clay		55		60		14. Well head completion: 8 inches above grade ☐ Pitless adapter	
Fine sand		60		65		15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.	
Sand and clay mixed		65		70		16. Nearest source of possible contamination: ft. 0 Direction None Type X Well disinfected upon completion? ☐ Yes ☒ No	
Fine sand		70		75		17. Pump: ☒ Not installed Manufacturer's name Not installed Model number Not installed HP Not installed Volts Not installed Length of drop pipe Not installed ft. capacity Not installed g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
Fine sand, little clay		75		80		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Darling Drilling Co. 189 Business name License No. Address 1011 W. 4th Hutchinson, Ks Signed Donald R. Darling 8/5/77 Authorized representative	
Med. sand, little clay		80		90			
Small gravel		90		95			
Small gravel		95		100			
Fine sand		100		105			
(Use a second sheet if needed)							
18. Elevation:		19. Remarks:					
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley							