


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Harvey	Fraction NW 1/4 SE 1/4 SE 1/4	Section number 27	Township number T 24 S	Range number R 3 E
2. Distance and direction from nearest town or city:			3. Owner of well: Fred Soper			
Street address of well location if in city: 1 S. 1E. Patterson			R.R. or street: 2541 Bobwhite			
			City, state, zip code: Wichita, Ks			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 30 in. Completion date 5/30/79		
		Open field		Well depth 53 ft.		
5. Type and color of material		From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug		
Topsoil		0	1	☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
Fine Sand		1	6	8. Use: ☒ Domestic ☐ Public supply ☐ Industry		
Med. Sand		6	53	☒ Irrigation ☐ Air conditioning ☐ Stock		
				☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material C-Asb Height: Above or below		
				Threaded ☐ Welded ☐ Surface 12 in.		
				RMP ☐ PVC ☐ Weight ☐ lbs./ft.		
				Dia. 46 in. to 53 ft. depth Wall Thickness: inches or		
				Dia. ☐ in. to ☐ ft. depth gage No. 3/4"		
				10. Screen: Manufacturer's name Johnson		
				Type Cement-Asb Dia. ☐		
				Slot/gauze 1/4" Length 19 1/2		
				Set between 33 1/2 ft. and 53 1/2 ft.		
				☐ ft. and ☐ ft.		
				Gravel pack? ☒ Size range of material 3/8		
				11. Static water level: ☐ mo./day/yr.		
				18 ft. below land surface Date 5/30/79		
				12. Pumping level below land surfaces:		
				25 ft. after 1 hrs. pumping 300 g.p.m.		
				☐ ft. after ☐ hrs. pumping ☐ g.p.m.		
				Estimated maximum yield 600 g.p.m.		
				13. Water sample submitted: ☐ mo./day/yr.		
				☐ Yes ☒ No Date ☐		
				14. Well head completion:		
				☐ Pitless adapter 12 inches above grade		
				15. Well grouted? ☒		
				With: ☐ Neat cement ☐ Bentonite ☒ Concrete		
				Depth: From 0 ft. to 10 ft.		
				16. Nearest source of possible contamination: none		
				ft. ☐ Direction ☐ Type ☐		
				Well disinfected upon completion? ☐ Yes ☒ No		
				17. Pump: ☐ Not installed		
				Manufacturer's name Peerless		
				Model number 9301 HP 15 Volts ☐		
				Length of drop pipe 40 ft. capacity 600 g.p.m.		
				Type:		
				☐ Submersible ☒ Turbine		
				☐ Jet ☐ Reciprocating		
				☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography:				This well was drilled under my jurisdiction and this report		
☐ Hill				is true to the best of my knowledge and belief.		
☐ Slope				Weninger Irrigation 238		
☒ Upland				Business name Maize License No. ☐		
☐ Valley				Address ☐		
				Signed X. Weninger Date 6/26/79		
				Authorized representative		