


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County HARVEY	Fraction 1/4 NE 1/4 SE 1/4	Section number 28	Township number T 24 S R 3W E 1/4
2. Distance and direction from nearest town or city: 4 N, 1 E, 1/4 N, 1/8 back into field of Mt. Hope, Kansas		3. Owner of well: R.L. Hanna R.R. or street: R.R. #2 City, state, zip code: Burrton, Kansas			
4. Locate with "X" in section below: 		Sketch map:		6. Bore hole dia. 14 in. Completion date _____ Well depth 87 ft. 7-11-78	
5. Type and color of material		From	To	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Topsoil		0	2	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Sandy Soil		2	6	9. Casing: Material PVC Height: Above or below 11 Threaded _____ Welded _____ Surface 12 in. RMP _____ PVC ☒ Weight 5.47 lbs./ft.	
Sandy Clay		6	15	Dia. 8 in. to 87 ft. depth Wall Thickness: inches or _____ Dia. _____ in. to _____ ft. depth gage No. .332	
Medium Sand		15	20	10. Screen: Manufacturer's name PVC NSF Approved 160 PSI Type PVC 160 PSI Dia. 8" Slot/groove .06 Length 25' Set between 62 ft. and 87 ft. Gravel pack? yes Size range of material 1/4-1/8"	
Coarse Sand and Gravel		20	30	11. Static water level: _____ mo./day/yr. 11 ft. below land surface Date 7-11-78	
Sand with Clay Streaks		30	40	12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.	
Fine Sand		40	60	13. Water sample submitted: _____ mo./day/yr. ☐ Yes ☐ No Date _____	
Medium to Fine Sand		60	87	14. Well head completion: capped _____ Pitless adapter 12 inches above grade	
(Use a second sheet if needed)				15. Well grouted? yes 1-2 Fine Sand Mix With: _____ Neat cement ☒ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.	
				16. Nearest source of possible contamination: _____ ft. _____ Direction _____ Type NONE Well disinfected upon completion? ☒ Yes ☐ No	
				17. Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: _____ Submersible _____ Turbine _____ Jet _____ Reciprocating _____ Centrifugal _____ Other	
18. Elevation:	19. Remarks: Flat Ground		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name _____ License No. 67209 Address Wichita, Kansas Signed M. Arnold Date 7-31-78 Authorized Representative		