

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Harvey</u>	Fraction <u>NN 1/4 SE 1/4 NE 1/4</u>	Section number <u>34</u>	Township number <u>T 24 S R 3 E W</u>	Range number <u>3</u>
2. Distance and direction from nearest town or city: Street address of well location if in city: <u>15 IE 1/4 S Patterson</u>				3. Owner of well: <u>Fred Soper</u> R.R. or street: <u>2541 Bobwhite</u> City, state, zip code: <u>Wichita, Ks.</u>		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>30</u> in. Completion date <u>4/2/79</u> Well depth <u>50</u> ft.		
		<u>open field</u>		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From To		8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
<u>Topsoil</u> <u>Fine Sand</u> <u>Fine - Med Sand</u>		<u>0 1</u> <u>1 7</u> <u>7 50</u>		9. Casing: Material <u>C-Asb</u> Height: <u>Above</u> or below Threaded ☐ Welded ☐ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. <u>16</u> in. to <u>50</u> ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gauge No. <u>314"</u>		
				10. Screen: Manufacturer's name <u>Johnson</u> Type <u>Cement-Asb</u> Dia. <u>16"</u> Slot/gauze <u>1/4"</u> Length <u>19 1/2'</u> Set between <u>30 1/2</u> ft. and <u>50</u> ft. ft. and ☐ ft. Gravel pack? ☒ Size range of material <u>3/8</u>		
				11. Static water level: ☐ mo./day/yr. <u>19</u> ft. below land surface Date <u>6/2/79</u>		
				12. Pumping level below land surfaces: <u>26</u> ft. after <u>1</u> hrs. pumping <u>300</u> g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield <u>600</u> g.p.m.		
				13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐		
				14. Well head completion: ☐ Pitless adapter <u>12</u> inches above grade		
				15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
				16. Nearest source of possible contamination: <u>none</u> ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No		
				17. Pump: ☐ Not installed Manufacturer's name <u>Peerless</u> Model number <u>9302</u> HP <u>15</u> Volts ☐ Length of drop pipe <u>40</u> ft. capacity <u>600</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
				(Use a second sheet if needed)		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Weninger Irr.</u> <u>238</u> Business name <u>Maize</u> License No. <u>1/4 1/4</u> Address <u>K. Weninger</u> Signed <u>K. Weninger</u> Date <u>4/24/79</u> Authorized representative		
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						