


1 LOCATION OF WATER WELL: County: HARVEY	Fraction SE 1/4 SE 1/4 SW 1/4	Section Number 03	Township Number 24 SOUTH	Range Number 3 WEST
---	----------------------------------	----------------------	-----------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
EB13B IS LOCATED 18 FEET NORTH AND 2375 FEET EAST OF PRAIRIE LAKE ROAD AND SW 48TH INTERSECTION

2 WATER WELL OWNER: EQUUS BEDS GROUNDWATER MANAGEMENT DISTRICT RR#, St. Address, Box #: 313 SPRUCE STREET City, State, ZIP Code HALSTEAD, KS 67056	Board of Agriculture, Division of Water Resources Application Number: N/A
--	--

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 	4 DEPTH OF COMPLETED WELL 90 feet Depth Groundwater Encountered 1 feet 2 feet 3 feet WELL'S STATIC WATER LEVEL 10.68 feet below land surface measured on 11/28/00 mo/day/yr Pump test data: Well water was feet after hrs pumping gpm Estimated Yield gpm: Well water was feet after hrs pumping gpm Bore Hole Diameter 6.0 inch to 92 feet and inch to feet WELL WATER IS USED AS: ☐ 1 Domestic ☐ 3 Feedlot ☐ 5 Public water supply ☐ 8 Air conditioning ☐ 11 Injection ☐ 2 Irrigation ☐ 4 Industrial ☐ 6 Oil field water supply ☐ 9 Dewatering ☐ 12 Other (specify below) ☐ 7 Lawn and garden only ☒ 10 Monitoring well EB13B Was a chemical/bacteriological sample submitted to Department? NO ; If yes, when mm/dd/yy sample was submitted Water Well Disinfected? NO
--	---

5 TYPE OF BLANK CASING USED: ☒ 1 Steel ☐ 3 RMP (SR) ☒ 2 PVC ☐ 4 ABS ☐ 7 Fiberglass Blank casing diameter STEEL 2 inches to 7.0 feet, Diameter PVC 2 inches to 80 feet, Diameter in to feet Casing height ABOVE land surface 36 inches, weight pounds/foot Wall thickness or gauge No TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ 1 Steel ☐ 3 Stainless steel ☐ 5 Fiberglass ☒ 7 PVC ☐ 2 Brass ☐ 4 Galvanized steel ☐ 6 Concrete tile ☐ 8 RMP (SR) SCREEN OR PERFORATION OPENINGS ARE: ☐ 1 Continuous Slot ☒ 3 Mill Slot ☐ 5 Gauzed Wrapped ☐ 8 Saw Cut ☐ 2 Louvered shutter ☐ 4 Key Punched ☐ 6 Wire Wrapped ☐ 9 Drilled holes ☐ 7 Torch cut ☐ 10 Other (specify) SCREEN-PERFORATED INTERVALS: From 90 feet to 80 feet, From feet to feet, From feet to feet GRAVEL PACK INTERVALS: From 92 feet to 75 feet, From feet to feet, From feet to feet	CASING JOINTS ☒ Glued ☐ Clamped ☐ Welded ☒ Threaded ☐ 10 Asbestos-cement ☐ 11 Other (specify) ☐ 12 None used (open hole) ☐ 11 None (open hole)
---	---

6 GROUT MATERIAL: 1 Neat cement ☐ 2 Cement grout ☒ 3 Bentonite ☒ 4 Other ☐ Grout Intervals: From 2) 75 feet to 9 feet, From 3) 9 feet to 0 feet, From feet to feet What is the nearest source of possible contamination: ☒ 1 Septic tank ☐ 4 Lateral lines ☐ 7 Pit privy ☐ 2 Sewer lines ☐ 5 Cess pool ☐ 8 Sewage lagoon ☐ 3 Watertight sewer line ☐ 6 Seepage pit ☐ 9 Feedyard ☐ 10 Livestock pens ☐ 14 Abandoned water well ☐ 11 Fuel storage ☐ 15 Oil well/Gas well ☐ 12 Fertilizer storage ☐ 16 Other (specify below) ☐ 13 Insecticide storage
--

Direction from well? WEST How many feet? 700		LITHOLOGIC LOG		LITHOLOGIC LOG	
FROM	TO		FROM	TO	
0.0	3	LOAM, brown			
3.0	7	CLAY, gray			
7.0	15	SAND, tan, coarse			
15	17	CLAY, tan-gray			
17	27	SAND, tan, medium to coarse			
27	28	CLAY, tan-gray			
28	30	SAND, tan, medium-coarse			
30	34	CLAY, tan-gray,			
34	57	SAND, tan, fine to medium			
57	59	CLAY, gray-green			
59	87	SAND, tan, fine to medium			
87	88	CLAY, tan			
88	92	SAND, tan, medium to coarse			

7 OWNER'S CERTIFICATION: This water well was constructed on 10/17/00(mo/day/year) under my jurisdiction and this record is true to the best of my knowledge and belief. This Water Well Record was completed on 2/8/01(mo/day/year) under the business name of Equis Beds Groundwater Management District No. 2. Kansas Water Well License No. not applicable.
(Signature and Title)