

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Harvey	NW ¼ SE ¼ SE ¼	11	T 24 S	R 3 X/W

Distance and direction from nearest town or city street address of well if located within city?

3 miles South & 2 3/4 miles East of Burrton, KS

2 WATER WELL OWNER:	John Stutzman
RR#, St. Address, Box # :	7415 S. Hertzler Rd.
City, State, ZIP Code :	Halstead, KS 67056
Board of Agriculture, Division of Water Resources	Application Number: 27,803

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 153 ft. ELEVATION:
	Depth(s) Groundwater Encountered 1 ft. 2 ft. 3 ft. WELL'S STATIC WATER LEVEL 16 ft. below land surface measured on mo/day/yr 12/19/02 Pump test data: Well water was ft. after hours pumping gpm Est. Yield ... 1000 ... gpm: Well water was ft. after hours pumping gpm WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) ☒ Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No ☒ ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes ☒ No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued ☒ Clamped
1 Steel	3 RMP (SR)	9 Other (specify below)	Welded
☒ PVC	4 ABS	7 Fiberglass	Threaded
Blank casing diameter 1.6 in. to 62 ft., Dia 1.6 in. to 113-133 ft., Dia in. to ft.			
Casing height above land surface 12 in., weight 16.15 lbs./ft. Wall thickness or gauge No.500			
TYPE OF SCREEN OR PERFORATION MATERIAL:	☒ PVC	10 Asbestos-Cement	
1 Steel	3 Stainless Steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized Steel	6 Concrete tile	9 ABS
11 Other (Specify)			12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
1 Continuous slot	☒ Mill slot	6 Wire wrapped	9 Drilled holes
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify) ft.
SCREEN-PERFORATED INTERVALS: From 62 ft. to 113 ft., From 133 ft. to 153 ft.			
GRAVEL PACK INTERVALS: From 23 ft. to 153 ft., From ft. to ft.			

6 GROUT MATERIAL:	1 Neat cement	☒ Cement grout	3 Bentonite	4 Other
Grout Intervals: From 2 ft. to 23 ft., From ft. to ft., From ft. to ft.				
What is the nearest source of possible contamination:	10 Livestock pens	14 Abandoned water well		
1 Septic tank	4 Lateral lines	7 Pit privy	11 Fuel storage	15 Oil well/Gas well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	12 Fertilizer storage	☒ Other (specify below)
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	13 Insecticide storage	old well
Direction from well? West		How many feet? 50		

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	Topsoil			
4	10	Clay, brown			
10	41	Sand, coarse & gravel, green			
41	50	Clay, gray, sandy			
50	72	Sand, medium to coarse & gravel, green			
72	79	Clay, gray			
79	103	Sand, fine, tan			
103	127	Clay, gray, hard			
127	137	Clay, light gray, sandy			
137	153	Sand, fine, tan			
153	155	Clay, brown, hard			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 12/20/02 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's Licence No 138 This Water Well Record was completed on (mo/day/yr) 12/23/02 under the business name of Peterson Irrigation, Inc. by (signature) <i>Mike Peterson</i>
