

INSTRUCTIONS: Please fill in blanks and circle the correct answers. Send three copies to Kansas Department of Health and Environment, Bureau of Water, 1000 S W Jackson St., Ste. 420, Topeka, Kansas 66612-1367. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.

TEST HOLE REPORT

LAYNE Western, a Div. of
LAYNE Christensen
Wichita, Kansas

Contract Name: Wichita ASR	Test Hole No. RB2PZ (d)
	Date: July 19, 2006
	Driller: M. Leslie

Location of Test Hole:	Elevation of Test Hole:
	Static Water Level:
Page 1 of 3	
	Measured Hours After Completion

From	To	Description of Strata
0	5	gray, silty sand, very fine to coarse
5	10	gray, silty sand, very fine to coarse
10	15	gray, olive sand, very fine to coarse
15	20	gray, olive sand, very fine to coarse with gray clay lens
20	25	gray, olive sand, very fine to coarse
25	30	gray, olive sand, very fine to coarse with gravel
30	35	gray, olive sand, very fine to coarse with gravel
35	40	olive sand, fine to coarse with gravel
40	45	olive sand, fine to coarse with gravel
45	50	olive sand, fine to coarse with gravel, slight clay
50	55	olive sand, fine to coarse with gravel, slight clay
55	60	olive sand, fine to coarse with gravel, slight clay
60	65	olive sand, fine to coarse with gravel, slight clay
65	70	olive silty sand, very fine to coarse with gravel, slight clay
70	75	olive silty sand, very fine to coarse with gravel
75	80	olive silty sand, very fine to coarse with gravel
80	85	olive silty sand, very fine to coarse with gravel, slight clay
85	90	olive sand, very fine to coarse
90	95	olive sand, very fine to coarse with gravel, slight clay

TEST HOLE REPORT

LAYNE Western, a Div. of
LAYNE Christensen
Wichita, Kansas

Contract Name: Wichita ASR	Test Hole No. RB2PZ (d)
	Date: July 19, 2006
	Driller: M. Leslie

Location of Test Hole:	Elevation of Test Hole:
	Static Water Level:
Page 2 of 3	
	Measured Hours After Completion

From	To	Description of Strata
95	100	olive sand, very fine to coarse with gravel
100	105	olive sand, very fine to coarse with gravel
105	110	olive sand, very fine to coarse with gravel, slight clay
110	115	olive sand, very fine to coarse with gravel
115	120	olive sand, very fine to coarse with gravel
120	125	olive sand, very fine to coarse with gravel
125	130	olive sand, very fine to coarse with gravel, slight clay
130	135	olive sand, fine to coarse with gravel, with clay lens
135	140	olive sand, fine to coarse with gravel, with slight clay
140	145	olive sand, fine to coarse with gravel, with slight clay
145	150	olive sand, fine to coarse with gravel
150	155	olive sand, fine to coarse with gravel, with clay lens
155	160	olive, red sand, very fine to coarse with gravel, with clay lens
160	165	olive, red sandy silty clay, low to medium plastic, fine to medium sand
165	170	olive, red sandy silty clay, low to medium plastic, fine to medium sand
170	175	olive, red sandy silty clay, low to medium plastic, fine to medium sand
175	180	olive, red sandy silty clay, low to medium plastic, sand lens
180	185	olive, red sandy silty clay, low to medium plastic
185	190	olive, red sandy silty clay, low to medium plastic, fine to med. sand

TEST HOLE REPORT

LAYNE Western, a Div. of
LAYNE Christensen
Wichita, Kansas

Contract Name: Wichita ASR	Test Hole No. RB2PZ (d)
	Date: July 19, 2006
	Driller: M. Leslie

Location of Test Hole:	Elevation of Test Hole:
	Static Water Level:
Page 3 of 3	
	Measured Hours After Completion

From	To	Description of Strata
190	195	olive, red sandy silty clay, low to medium plastic, sand lens
195	200	olive, red sandy silty clay, low to medium plastic, sand lens
200	205	olive silty sand, very fine to coarse, slight clay
205	210	olive silty sand, very fine to coarse, clay lens
210	215	olive silty sand, very fine to medium
215	220	olive silty sand, very fine to medium
220	225	olive silty sand, very fine to medium
225	230	olive silty sand, very fine to medium
230	235	olive silty sand, very fine to medium
235	240	olive silty sand, very fine to medium
240	245	olive silty sand, very fine to medium
245	250	olive sand, very fine to medium
250	255	olive sand, very fine to medium
255	260	olive sand, very fine to coarse