

County: Harvey Fraction: NENESE Sec. 15 T 24 S R 3 W

CORRECTION(S) TO WATER WELL COMPLETION RECORD (WWC-5) - to rectify lacking or incorrect information

Owner: Equus Beds GMD 2

If corrected, location was listed as:

Location changed to:

Section-Township-Range: 15-24S-3W

15-24S-3W

Fraction (1/4 1/4 1/4): SE SE SE NE

NE NE NE SE

Other changes: Initial statements: Latitude: 37.96332, Longitude: 97.62856,
Datum: NAD 27.

Changed to: Latitude: 37.963251, Longitude: -97.628907, Datum: NAD 27.

Comments: Well ID: EB 19A

Verification method: Latitude & longitude taken from GMD #2 GPS units.
Well ID from GMD #2.

Initials: DPA Date: 5/16/2018

Submitted by: ☒ Kansas Geological Survey, Data Resources Library, 1930 Constant Avenue, Lawrence, KS 66047-3724
☐ Kansas Dept. of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: <u>Harvey</u>	Fraction SE ¼ SE ¼ SE ¼ NE ¼	Section Number 15	Township No. T 24 S	Range Number R 3 ☐ E ☒ W
---	---------------------------------	----------------------	------------------------	--

Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐.

1 mile N. 1 1/2 E. 1/2 N of Patterson, Ks.

2 WATER WELL OWNER: Equus Beds GMD 2 RR#, Street Address, Box #: 313 Spruce Street City, State, ZIP Code : Halstead, Kansas 67056	Global Positioning System (GPS) information: Latitude: <u>37.96332</u> (in decimal degrees) Longitude: <u>097.62856</u> (in decimal degrees) Elevation: <u>1411</u> Datum: ☐ WGS 84, ☐ NAD 83, ☒ NAD 27 Collection Method: ☒ GPS unit (Make/Model: <u>Garmin csx</u>) ☐ Digital Map/Photo, ☒ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m
--	--

3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="margin: auto;"> <tr> <td style="width: 20px;">NW</td> <td style="width: 20px;">NE</td> </tr> <tr> <td style="width: 20px;">SW</td> <td style="width: 20px;">SE</td> </tr> </table> S -----1 mile-----	NW	NE	SW	SE	4 DEPTH OF COMPLETED WELL <u>37</u> ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL..... ft. below land surface measured on mo/day/yr. <u>8-31-09</u> Pump test data: Well water was..... ft. after..... hours pumping..... gpm EST. YIELD..... gpm. Well water was..... ft. after..... hours pumping..... gpm Bore Hole Diameter <u>6 1/2</u> in. to <u>37</u> ft., and..... in. to..... ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☒ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well ☐ Observation well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted..... Water well disinfected? ☐ Yes ☒ No
NW	NE				
SW	SE				

5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☒ Other Galvanized

CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☒ Threaded

Casing diameter 2 in. to 7 ft., Diameter 2 in. to 27 ft., Diameter..... in. to..... ft.
 Casing height above land surface 36 in., Weight SCH 40 lbs./ft., Wall thickness or gauge No. 154

TYPE OF SCREEN OR PERFORATION MATERIAL:
☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify).....
☐ Brass ☐ Galvanized Steel ☐ None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:
☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole)
☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify).....

SCREEN-PERFORATED INTERVALS: From 27 ft. to 37 ft., From..... ft. to..... ft.
 From..... ft. to..... ft., From..... ft. to..... ft.

GRAVEL PACK INTERVALS: From 37 ft. to 22 ft., From..... ft. to..... ft.
 From..... ft. to..... ft., From..... ft. to..... ft.

6 GROUT MATERIAL: ☒ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other.....

Grout Intervals: From 22 ft. to 19 ft., From 19 ft. to 6 ft., From 6 ft. to 0 ft.
neat cement *bentonite*

What is the nearest source of possible contamination:
☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below)
☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well
☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well none

Direction from well..... Distance from well.....

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
0	2	Top Soil			
2	12	Brown Clay			
12	37	Medium Sand & Gravel			
37	38	Clay			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 8-31-09 and this record is true to the best of my knowledge and belief.
 Kansas Water Well Contractor's License No. 134 This Water Well Record was completed on (mo/day/year) 9-04-09
 under the business name of Rosencrantz-Bemis Ent. by (signature) Janeen Dodson

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at <http://www.kdheks.gov/waterwell/index.html>.