

KSA 82a-1212

Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: OB42S	
LOCATION: SE ¼ SE ¼ SE ¼ NE ¼, 11-T24S-R3W, Harvey Co., KS	
LATITUDE: 37° 58' 42.7"	
LONGITUDE: 097° 36' 39.9"	
FOOTAGES: 2872 feet from the South section line and 209 feet from the East section line.	
DATE: 10-28-09	DRILLED BY: CL

SWL:

PWL:

from feet - to feet

0	5	Clay
5	20	Fine, medium and coarse sand and fine gravel
20	40	Fine, medium and coarse sand and fine and medium gravel

Well Depth: 38'
Bore Hole Dia: 6"

Plain casing: 28' of 2"
Perf. casing: 10' of 2"

slot size: .020"

Gravel pack from 23' to 38'
Bentonite from 0' to 23'

dh