

Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: OB45D	
LOCATION: NE ¼ NE ¼ NE ¼ SE ¼, 23-T24S-R3W, Harvey Co., KS	
LATITUDE: 37° 56' 53.7"	
LONGITUDE: 097° 36' 40.0"	
FOOTAGES: 2512 feet from the South section line and 172 feet from the East section line.	
DATE: 10-27-09	DRILLED BY: CL

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	5	Topsoil and clay
5	20	Fine, medium and coarse sand and fine gravel
20	40	Fine, medium and coarse sand and fine and medium gravel
40	46	Fine, medium and coarse sand and fine gravel
46	55	Fine sand
55	65	Clay
65	95	Fine, medium and coarse sand and fine gravel
95	100	Clay
100	110	Fine, medium and coarse sand and clay layers
110	115	Clay
115	125	Fine, medium and coarse sand
125	129	Clay
129	130	Sand
130	136	Fine, medium and coarse sand
136	140	Clay
140	170	Fine and medium sand
170	180	Clay

Well Depth: 170'
Bore Hole Dia: 6"

Plain casing: 150' of 2"
Perf. casing: 20' of 2" slot size: .020"

Gravel pack from 140' to 170'
Bentonite from 0' to 140'