

1 LOCATION OF WATER WELL: County: Harvey		Fraction SW 1/4 SW 1/4 SW 1/4 SE 1/4	Section Number 24	Township No. T 24 S	Range Number R 3 ☐ E ☒ W
Street Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ 1/2 mile west of intersection SW 84th St. and 215th St. W. on the north side of SW 84th			Global Positioning System (GPS) information: Latitude: 37° 56' 31.1" (in decimal degrees) Longitude: 097° 36' 3.2" (in decimal degrees) Elevation: Datum: ☐ WGS 84. ☒ NAD 83. ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: Garmin) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m		

2 WATER WELL OWNER: City of Wichita RR#. Street Address, Box #: 455 North Main Street City, State, ZIP Code : Wichita, KS 67202

3 LOCATE WELL WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 169 ft.

Depth(s) Groundwater Encountered (1) 21.3 ft. (2) ft. (3) ft.

WELL'S STATIC WATER LEVEL 21.3 ft. below land surface measured on mo/day/yr. 10/26/09

Pump test data: Well water was ft. after hours pumping gpm

EST. YIELD gpm. Well water was ft. after hours pumping gpm

Bore Hole Diameter 6 in. to 180 ft. and in. to ft.

WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well
☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☒ Other (Specify below)
☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well ☐ Observation

Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No

If yes, mo/day/yr sample was submitted.....

Water well disinfected? ☐ Yes ☒ No

5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other

CASING JOINTS: ☒ X ☒ X ☒ X ☐ Clamped ☐ Welded ☒ Threaded

Casing diameter 2 in. to 149 ft., Diameter in. to ft.

Casing height above land surface 24 in., Weight 703 lbs./ft., Wall thickness or gauge No. 154

TYPE OF SCREEN OR PERFORATION MATERIAL:
☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify)
☐ Brass ☐ Galvanized Steel ☐ None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:
☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole)
☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify)

SCREEN-PERFORATED INTERVALS: From 149 ft. to 169 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

GRAVEL PACK INTERVALS: From 139 ft. to 169 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other

Grout Intervals: From 0 ft. to 139 ft., From ft. to ft., From ft. to ft.

What is the nearest source of possible contamination:
☒ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below)
☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well
☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well

Direction from well Distance from well Over 1000 feet

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
		Log attached			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 10/26/2009 and this record is true to the best of my knowledge and belief.

Kansas Water Well Contractor's License No. 755 This Water Well Record was completed on (mo/day/year) 11/11/2009 under the business name of Sargent Drilling by (signature) [Signature]

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at <http://www.kdheks.gov/waterwell/index.html>.

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: OB47D	
LOCATION: SW ¼ SW ¼ SW ¼ SE ¼, 24-T24S-R3W, Harvey Co., KS	
LATITUDE: 37° 56' 31.1"	
LONGITUDE: 097° 36' 3.2"	
FOOTAGES: 223 feet from the South section line and 2541 feet from the East section line.	
DATE: 10-26-09	DRILLED BY: CL

SWL:

PWL:

from feet - to feet

0	5	Topsoil and clay
5	20	Fine, medium and coarse sand and fine gravel
20	40	Fine, medium and coarse sand and fine and medium gravel
40	44	Fine, medium and coarse sand and fine gravel
44	56	Clay
56	60	Fine, medium and coarse sand
60	75	Fine, medium and coarse sand and fine gravel
75	76	Clay
76	80	Fine, medium and coarse sand and fine gravel
80	104	Fine, medium and coarse sand
104	106	Clay
106	115	Fine, medium and coarse sand
115	120	Fine sand
120	169	Fine and medium sand
169	180	Clay and sand layers

Well Depth: 169'
Bore Hole Dia: 6"

Plain casing: 149' of 2"
Perf. casing: 20' of 2" slot size: .020"

Gravel pack from 139' to 169'
Bentonite from 0' to 139'

dh