
KSA 82a-1212

Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Irrigation

WELL AND PUMP SERVICE

PO Box 268
Holdrege, NE 68949

825 Brewster Road

Phone: (308) 995-6143
1-800-860-2946

TEST HOLE LOG

CUSTOMER: Wichita, KS	
WELL ID: OB43S	
LOCATION: SE ¼ SE ¼ SE ¼ SE ¼, 11-T24S-R3W, Harvey Co., KS	
LATITUDE: 37° 58' 15.6"	
LONGITUDE: -97° 36' 39.9"	
FOOTAGES: 132' North of south section line and 214 West of the east line	
DATE: 10/28/09	DRILLED BY: Kyle Schoff, Doug Rezac, Cody Hanson

SWL:

PWL:

GPM:

from feet - to feet

0	5	Top soil and clay
5	10	Coarse sand to fine gravel
10	20	Coarse sand to medium gravel
20	35	Coarse sand to fine gravel
35	40	Coarse sand to fine gravel with traces of sandy clay

Well Information:

Well depth: 37'
Plain casing: 27'
Perf. Set: 27'-37'

Bore hole: 6"
Perf. casing: 10'
Gravel: 22-37'

Casing size: 2"
Slot size: .020"
Grout: 0-22'