

County: Harvey Fraction SW SW SW SE Sec. 11 T 24 S R 3 E(W)

CORRECTION(S) TO WATER WELL COMPLETION RECORD (WWC-5)

(to rectify lacking or incorrect information)

Owner: City of Wichita

Location was listed as:

Location changed to:

Section-Township-Range: 12-24S-3W

11-24S-3W

Fraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): SW SW SW SE

SW SW SW SE

Other changes: Initial statements: _____

Changed to: _____

Comments: _____

Verification method: Latitude & longitude & KGS' LEO conversion tool,
written description, & mapping tool & aerial photos on
KGS website.

initials: DRK date: 4/15/2015

Submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726
to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

--

Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Irrigation

WELL AND PUMP SERVICE

PO Box 268
Holdrege, NE 68949

825 Brewster Road

Phone: (308) 995-6143
1-800-860-2946

TEST HOLE LOG

CUSTOMER: Wichita, KS	
WELL ID: OB44D	
LOCATION: SW ¼ SW ¼ SW ¼ SE ¼, 12-T24S-R3N, Harvey Co., KS	
LATITUDE: 37° 58' 15.9"	
LONGITUDE: -97° 37' 09.1"	
FOOTAGES: 167' from the South section line and 2552 feet from the East section line.	
DATE: 10/27/09	DRILLED BY: Kyle Schoff, Doug Rezac, Cody Hanson

SWL:

PWL:

GPM:

from feet - to feet

0	3	Top soil and clay
3	5	Sandy clay and coarse sand
5	15	Sandy clay and coarse sand and medium gravel
15	20	Coarse sand to medium gravel
20	25	Sandy clay and coarse sand
25	30	Sandy clay
30	35	Coarse sand and sandy clay
35	40	Sandy clay
40	45	Sandy clay and medium sand
45	50	Sandy clay
50	55	Sandy clay and medium sand
55	60	Sandy clay and medium sand to fine gravel
60	70	Medium sand to fine gravel with traces of sandy clay
70	80	Medium sand to fine gravel
80	95	Coarse sand to fine gravel
95	100	Fine to medium sand and fine gravel

Well Information:

Well depth: 95'
Plain casing: 75'
Perf. Set: 75'-95'

Bore hole: 6"
Perf. casing: 20'
Gravel: 70-95'

Casing size: 2"
Slot size: .020"
Grout: 0-70"