

Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: RR05 Supply Well	
LOCATION: NE ¼ NE ¼ NE ¼ NE ¼, 2-T24S-R3W, Harvey Co., KS	
LATITUDE: 37° 59' 56"	
LONGITUDE: 097° 36' 39"	
FOOTAGES:	
DATE: 2-4-10	DRILLED BY:

SWL: 21'
PWL: 300 @ 62'

<u>from feet</u>	<u>- to feet</u>	
0	2	Topsoil
2	22	Clay
22	40	Coarse sand and fine gravel
40	52	Coarse sand
52	72	Clay
72	80	Gravel

Well Depth: 80'
Bore Hole Dia: 10"

Plain casing: 40' of 6"
Perf. casing: 40' of 6" slot size: .025"

Gravel pack from 25' to 80'
Hole plug from 0' to 25'

dh