
Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: RR05	
LOCATION: NE ¼ NE ¼ NE ¼ NE ¼, 2-T24S-R3W, Harvey Co., KS	
LATITUDE: 37° 59' 57.0"	
LONGITUDE: 097° 36' 39.8"	
FOOTAGES: 5145 feet from the South section line and 202 feet from the East section line.	
DATE: 10-12-09	DRILLED BY: Dave

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	2	Sandy topsoil
2	72	Medium gravel
72	75	Clay
75	80	Medium gravel
80	100	Fine gravel
100	116	Coarse sand
116	118	Clay
118	135	Coarse sand
135	140	Coarse sand, tight
140	160	Medium sand, tight with clay stringers
160	164	Medium sand
164	176	Sandy clay
176	200	Medium sand
200	232	Coarse sand
232	243	Clay
243	249	Medium sand
249	251	Clay
251	266	Fine gravel
266	280	Shale

Sargent Drilling

INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL, INDUSTRIAL AND AGRICULTURAL
PUMP AND WELL SERVICE

P.O. Box 367
846 S. 13th Street
Geneva, NE 68361-0367

Phone: (402) 759-3902
Toll Free: (888) 496-3902
Fax: (402) 759-4960

RR05 – Section 5

	FROM	TO
Steel Recharge Casing – 4" - .337" wall Grade B	0'	72'
Carbon Steel Casing – 18" - .500" wall A53 Grade B	0'	75'
Stainless Steel Casing – 18" - .500" wall ASTM A312	75'	80'
Stainless Steel Screen – 18" - .500" wall .045 slot 304 Stainless	80'	100'
Stainless Steel Casing – 18" - .500" wall ASTM A312	100'	105'
Carbon Steel Casing – 18" - .500" wall A53 Grade B	105'	115'
Stainless Steel Casing – 18" - .500" wall ASTM A312	115'	120'
Stainless Steel Screen – 18" - .500" wall .045 slot 304 Stainless	120'	132'
Stainless Steel Casing – 18" - .500" wall ASTM A312	132'	137'
Carbon Steel Casing – 18" - .500" wall A53 Grade B	137'	178'
Stainless Steel Casing – 18" - .500" wall ASTM A312	178'	183'
Stainless Steel Screen – 18" - .500" wall .045 slot 304 Stainless	183'	222'
Stainless Steel Casing – 18" - .500" wall ASTM A312	222'	240'
Stainless Steel Screen – 18" - .500" wall .045 slot 304 Stainless	240'	264'
Stainless Steel Casing – 18" - .500" wall ASTM A312	264'	269'