
KSA 82a-1212 Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 627
263 South 23rd Street

Broken Bow, Nebraska
68822

Phone: (308) 872-5125
FAX (308) 872-3050

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MW2D	
LOCATION: SE ¼ SE ¼ SE ¼ SW ¼, 13-T24S-R03W, Harvey Co., KS	
LATITUDE: 37° 57' 21.6"	
LONGITUDE: 097° 36' 05.2"	
FOOTAGES: 42 feet from the South section line and 2701 feet from the East section line.	
DATE: 2-3-10	DRILLED BY: DG

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	17	Clay
17	20	Medium Sand
20	30	Fine Gravel / Clay Layers
30	40	Medium Gravel
40	60	Coarse Sand / Fine Gravel with Clay Stringers
60	71	Fine Gravel
71	75	Clay
75	80	Coarse Sand
80	114	Fine Gravel
114	121	Clay
121	140	Fine Sand
140	146	Fine Gravel
146	147	Clay
147	158	Medium Sand
158	163	Clay
163	169	Fine Sand
169	227	Clay
227	240	Fine Sand with Clay Stringers
240	268	Medium Sand
268	277	Clay
277	280	Fine Sand

Well Information:

Well Depth: 265'	Bore Hole Dia: 6"	Casing size: 2"
Plain casing: 245' of 2"	Perf. casing: 20' of 2"	Slot size: .020"
Perf. Set: 245 to 265	Gravel: 238' to 265'	EZ Grout: 30 to 238
		Hole Plug: 0' to 30'