

Corrected

--

KSA 82a-1212

Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 627
263 South 23rd Street

Broken Bow, Nebraska
68822

Phone: (308) 872-5125
FAX (308) 872-3050

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MR56 Supply Well	
LOCATION: SW ¼ SW ¼ SW ¼ SW ¼, 13-T24S-R03W, Harvey Co., KS	
LATITUDE: 37° 57' 22.0"	
LONGITUDE: 097° 36' 36.1"	
FOOTAGES: 83 feet from the South section line and 5176 feet from the East section line.	
DATE: 2-1-10	DRILLED BY: DG

SWL: 21
PWL: 300 ft 60

<u>from feet</u>	<u>- to feet</u>	
0	2	Top Soil
2	8	Clay
8	20	Coarse Sand
20	32	Fine Gravel
32	35	Clay
35	54	Fine Gravel
54	60	Clay
60	80	Gravel

Well Information:

Well Depth: 80'
Plain casing: 40' of 6"
Perf. Set: 40 to 80'

Bore Hole Dia: "
Perf. casing: 40' of 6"
Gravel: 20' to 80'

Casing size: 6"
Slot size: .025"
Hole Plug: 0' to 20'

mp