
Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MR56	
LOCATION: SW ¼ SW ¼ SW ¼, 13-T24S-R3W, Harvey Co., KS	
LATITUDE: 37° 57' 22.9"	
LONGITUDE: 097° 36' 36.2"	
FOOTAGES: 174' from the south section line and 5184' from the East section line.	
DATE: 1-5-10	DRILLED BY: CL

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	6	Topsoil and clay
6	20	Fine, medium and coarse sand and fine, medium and coarse gravel
20	40	Fine, medium and coarse sand and fine and medium gravel with blue clay strips
40	55	Fine, medium and coarse sand and fine and medium gravel
55	70	Tan clay
70	100	Fine, medium and coarse sand and fine gravel
100	150	Fine, medium and coarse sand and fine and medium gravel
150	160	Fine, medium and coarse sand and blue clay strips
160	170	Fine, medium and coarse sand
170	180	Clay

Sargent Drilling

INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL, INDUSTRIAL AND AGRICULTURAL
PUMP AND WELL SERVICE

P.O. Box 367
846 S. 13th Street
Geneva, NE 68361-0367

Phone: (402) 759-3902
Toll Free: (888) 496-3902
Fax: (402) 759-4960

MR56 – Secion 5

	FROM	TO
Steel Recharge Casing – 4” .337” wall Grade B	0’	40’
Carbon Steel Casing – 18” - .500” wall A53 Grade B	0’	70’
Stainless Steel Casing – 18” - .500” wall ASTM A312	70’	75’
Stainless Steel Screen – 18” - .500” wall .090” slot 304 Stainless	75’	150’
Stainless Steel Casing – 18” - .500” wall ASTM A312	150’	155’