
KSA 82a-1212

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 627
263 South 23rd Street

Broken Bow, Nebraska
68822

Phone: (308) 872-5125
FAX (308) 872-3050

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: OB MR56D	
LOCATION: SW ¼ SW ¼ SW ¼ SW ¼, 13-T24S-R03W, Harvey Co., KS	
LATITUDE: 37° 57' 23.5"	
LONGITUDE: 097° 36' 36.0"	
FOOTAGES: 234 feet from the South section line and 5169 feet from the East section line.	
DATE: 2-1-10	DRILLED BY: DG

SWL: 19.
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	2	Top Soil
2	8	Clay
8	35	Fine Gravel
35	36	Clay
36	40	Fine Gravel
40	56	Fine Gravel / Medium Gravel
56	60	Silty Clay
60	73	Clay
73	140	Fine Gravel
140	160	Coarse Sand / Fine Gravel with Clay Stringers
160	171	Medium Sand
171	180	Clay

Well Information:

Well Depth: 170'
Plain casing: 150' of 2"
Perf. Set: 150 to 170'

Bore Hole Dia: 6"
Perf. casing: 20' of 2"
Gravel: 145' to 170'

Casing size: 2"
Slot size: .020"
EZ Grout: 0' to 145'

mp