
Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MR-45	
LOCATION: NE ¼ NE ¼ NE 1/4, SE 1/4., 23-T24S-R3W, Harvey Co., KS	
LATITUDE: 37° 56' 53.4"	
LONGITUDE: 097° 36' 39.0"	
FOOTAGES: 2483 feet from the South section line and 92 feet from the East section line.	
DATE: 10-13-09	DRILLED BY: Dave

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	2	Topsoil
2	12	Clay
12	52	Medium gravel
52	64	Clay
64	91	Fine gravel
91	93	Clay
93	98	Fine gravel
98	105	Clay
105	112	Fine gravel
112	115	Clay
115	124	Fine gravel
124	142	Clay
142	172	Coarse sand
172	178	Clay
178	180	Shale
180	190	Clay

Sargent Drilling

INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL, INDUSTRIAL AND AGRICULTURAL
PUMP AND WELL SERVICE

P.O. Box 367
846 S. 13th Street
Geneva, NE 68361-0367

Phone: (402) 759-3902
Toll Free: (888) 496-3902
Fax: (402) 759-4960

MR45 – Section 5

	FROM	TO
Steel Recharge Casing – 4” - .337” wall Grade B	0’	40’
Carbon Steel Casing – 18” - .500” wall A53 Grade B	0’	65’
Stainless Steel Casing – 18” - .500” wall ASTM A312	65’	70’
Stainless Steel Screen – 18’ - .500” wall .090 slot 304 Stainless	70’	90’
Stainless Steel Casing – 18” - .500” wall ASTM A312	90’	95’
Carbon Steel Casing – 18” - .500” wall A53 Grade B	95’	108’
Stainless Steel Casing – 18” - .500” wall ASTM A312	108’	113’
Stainless Steel Screen – 18” - .500” wall .090 slot 304 Stainless	113’	120’
Stainless Steel Casing – 18” - .500: wall ASTM A312	120’	125’
Carbon Steel Casing – 18” - .500” wall A53 Grade B	125’	135’
Stainless Steel Casing – 18” - .500” wall ASTM A312	135’	140’
Stainless Steel Screen – 18” - .500” wall .045 slot 304 Stainless	140’	168’
Stainless Steel Casing – 18” - .500” wall ASTM A312	168’	173’