
Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 627
263 South 23rd Street

Broken Bow, Nebraska
68822

Phone: (308) 872-5125
FAX (308) 872-3050

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MW4S	
LOCATION: SW ¼ SE ¼ SE ¼ SE ¼, 24-T24S-R03W, Harvey Co., KS	
LATITUDE: 37° 56' 29.6"	
LONGITUDE: 097° 35' 35.8"	
FOOTAGES: 67 feet from the South section line and 347 feet from the East section line.	
DATE: 2-2-10	DRILLED BY: DG

SWL: 10-5
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	2	Top Soil
2	9	Clay
9	20	Medium Gravel
20	36	Fine Gravel
36	37	Clay
37	48	Fine Gravel

Well Information:

Well Depth: 45'
Bore Hole Dia: 6"

Plain casing: 35' of 2"
Perf. casing: 10' of 2" slot size: .020"

Gravel pack from 30' to 45'
Bentonite from 0' to 30'

mp