

--

Check: ☐ White Copy, ☐ Blue Copy, ☐ Pink Copy

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: MR47	
LOCATION: SW ¼ SW ¼ SW ¼ SE ¼, 24-T24S-R3W, Harvey Co., KS	
LATITUDE: 37° 56' 30.4"	
LONGITUDE: 097° 36' 3.2"	
FOOTAGES: 152 feet from the South section line and 2541 feet from the East section line.	
DATE: 10-26-09	DRILLED BY: CL

SWL:
PWL:

<u>from feet</u>	<u>- to feet</u>	
0	14	Topsoil and sandy clay
14	20	Fine, medium and coarse sand and fine gravel
20	40	Fine, medium and coarse sand and fine and medium gravel
40	45	Blue clay
45	60	Fine, medium and coarse sand and fine gravel
60	67	Sand
67	72	Clay
72	90	Fine, medium and coarse sand
90	94	Blue clay
94	100	Fine, medium and coarse sand and fine gravel
100	104	Fine, medium and coarse sand
104	108	Clay
108	140	Fine, medium and coarse sand
140	160	Fine, medium and coarse sand and clay strips
160	171	Fine and medium sand
171	180	Clay

Sargent Drilling

INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL, INDUSTRIAL AND AGRICULTURAL
PUMP AND WELL SERVICE

P.O. Box 367
846 S. 13th Street
Geneva, NE 68361-0367

Phone: (402) 759-3902
Toll Free: (888) 496-3902
Fax: (402) 759-4960

MR47 – Section 5

	FROM	TO
Steel Recharge Casing – 4" - .337" wall Grade B	0'	40'
Carbon Steel Casing – 18" - .500" wall A53 Grade B	0'	50'
Stainless Steel Casing – 18" - .500" wall ASTM A312	50'	55'
Stainless Steel Screen – 18" - .500" wall .050 slot 304 Stainless	55'	90'
Stainless Steel Casing – 18" - .500" wall ASTM A312	90'	95'
Carbon Steel Casing - 18" - .500" wall A53 Grade B	95'	105'
Stainless Steel Casing – 18" - .500" wall ASTM A312	105'	110'
Stainless Steel Screen – 18" - .500" wall .030 slot 304 Stainless	110'	165'
Stainless Steel Casing – 18" - .500" wall ASTM A312	165'	170'

