

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

County: Harvey

Location listed as:

Section-Township-Range: 8-245-3W

Fraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): NE NE SW NE

Location changed to:

8-245-3W

NW NW SE NE

Other changes: Initial statements: _____

Changed to: _____

Comments: _____

verification method: Latitude & longitude, KGS' "LEO" conversion tool,
and mapping tool & aerial photos on KGS website.

initials: DR date: 12/8/2010

submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726
to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

43089

1 LOCATION OF WATER WELL: County: <u>Harvey</u>		Fraction <u>NE ¼ NE ¼ SW ¼ NE ¼</u>		Section Number <u>8</u>	Township No. <u>T 24 S</u>	Range Number <u>R 3</u> ☐ E ☒ W																																																																								
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ .				Global Positioning System (GPS) information: Latitude: <u>37.98138</u> (in decimal degrees) Longitude: <u>97.66983</u> (in decimal degrees) Elevation: <u>1457</u> Datum: ☐ WGS 84, ☐ NAD 83, ☒ NAD 27 Collection Method: ☒ GPS unit (Make/Model: <u>Garmin csx</u>) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																										
2 WATER WELL OWNER: <u>Beatrice M. O'Neal Trust</u> RR#, Street Address, Box #: <u>P.O. Box 913</u> City, State, ZIP Code : <u>Hutchinson, Kansas 67504</u>																																																																														
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="margin: auto; border-collapse: collapse;"> <tr> <td style="width: 20px; text-align: center;">W</td> <td style="width: 40px; height: 40px; text-align: center;">NW</td> <td style="width: 40px; height: 40px; text-align: center;">NE</td> <td style="width: 20px; text-align: center;">E</td> </tr> <tr> <td></td> <td style="text-align: center;">SW</td> <td style="text-align: center;">SE</td> <td></td> </tr> </table> S -----1 mile-----		W	NW	NE	E		SW	SE		4 DEPTH OF COMPLETED WELL 42 ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL <u>9</u> ft. below land surface measured on mo/day/yr. <u>4-20-10</u> Pump test data: Well water was..... ft. after..... hours pumping..... gpm EST. YIELD..... gpm. Well water was..... ft. after..... hours pumping..... gpm Bore Hole Diameter <u>30</u> in. to <u>42</u> ft., and..... in. to..... ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted..... Water well disinfected? ☒ Yes ☐ No																																																																				
W	NW	NE	E																																																																											
	SW	SE																																																																												
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other..... CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter <u>16</u> in. to <u>27</u> ft., Diameter..... in. to..... ft., Diameter..... in. to..... ft. Casing height above land surface <u>12</u> in., Weight <u>SCH 40</u> lbs./ft., Wall thickness or gauge No. <u>500</u> TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify)..... ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify)..... SCREEN-PERFORATED INTERVALS: From <u>27</u> ft. to <u>42</u> ft., From..... ft. to..... ft. From..... ft. to..... ft., From..... ft. to..... ft. GRAVEL PACK INTERVALS: From <u>42</u> ft. to <u>14</u> ft., From..... ft. to..... ft. From..... ft. to..... ft., From..... ft. to..... ft.																																																																														
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other..... Grout Intervals: From <u>14</u> ft. to <u>1</u> ft., From..... ft. to..... ft., From..... ft. to..... ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well <u>plugged irria. well</u> Direction from well <u>North</u> Distance from well <u>50</u>																																																																														
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="width:10%;">FROM</th> <th style="width:10%;">TO</th> <th style="width:40%;">LITHOLOGIC LOG</th> <th style="width:10%;">FROM</th> <th style="width:10%;">TO</th> <th style="width:20%;">LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>3</td> <td>Top soil</td> <td></td> <td></td> <td></td> </tr> <tr> <td>3</td> <td>7</td> <td>Brown clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>7</td> <td>13</td> <td>Medium sand & gravel</td> <td></td> <td></td> <td></td> </tr> <tr> <td>13</td> <td>16</td> <td>Bluish green clay & med. sand mix</td> <td></td> <td></td> <td></td> </tr> <tr> <td>16</td> <td>41</td> <td>Medium sand & gravel</td> <td></td> <td></td> <td></td> </tr> <tr> <td>41</td> <td>42</td> <td>Bluish green clay-hard</td> <td></td> <td></td> <td></td> </tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>							FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	3	Top soil				3	7	Brown clay				7	13	Medium sand & gravel				13	16	Bluish green clay & med. sand mix				16	41	Medium sand & gravel				41	42	Bluish green clay-hard																																	
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																									
0	3	Top soil																																																																												
3	7	Brown clay																																																																												
7	13	Medium sand & gravel																																																																												
13	16	Bluish green clay & med. sand mix																																																																												
16	41	Medium sand & gravel																																																																												
41	42	Bluish green clay-hard																																																																												
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) <u>4-20-2010</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>134</u> This Water Well Record was completed on (mo/day/year) <u>4-23-2010</u> under the business name of <u>Rosencrantz-Bemis Ent.</u> by (signature) <u>Ashley D. Adams</u>																																																																														
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each <u>constructed</u> well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																														