


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Gray	Township name Logan	Fraction Pivot SE 1/4	Section number 14	Town number T 24 S	Range number R 30 W
Distance and direction from nearest town or city: 1 3/4 west of Charleston, Ks. Street address of well location if in city:				3 Owner of well: Mrs. William Tegeler Address: (Not Known)		
Locate with "X" in section below: 				4 Well depth: 240 ft. Date of completion 4-20-75 Well diameter 26 in.		
2 Type and color of material				5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
				6 Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well		
				7 Casing: Material Steel Height: above/below Threaded ☐ Welded ☒ Surface 12 in. Diam. 16 in. to 24 ft. depth Drive shoe? ☐ Yes ☒ No _____ in. to _____ ft. depth		
				8 Screen: Manufacturer Johnson Division Type Galv. Dia. 16" Slot/Screen 100 Length 20' Set between 200 ft. and 220 ft. Perforations: 170-200, 220-240 Gravel pack ☒ Yes ☐ No Size range of material 1/2" down		
				9 Static water level: 119 ft. below land surface Date 4-20-75		
				10 Pumping level below land surfaces: 149 ft. after 2 hrs. pumping 760 g.p.m. 175 ft. after 4 hrs. pumping 1370 g.p.m. Estimated maximum yield 1300 g.p.m.		
				11 Water sample submitted: ☐ Yes ☒ No Date _____		
				12 Well head completion: ☐ Pitless adapter 12 Inches above grade		
				13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ Depth: From 0 ft. to 10 ft.		
				14 Nearest source of possible contamination: N/A ft. _____ Direction _____ Type _____ Well disinfected upon completion? ☐ Yes ☒ No		
				15 Pump: ☐ Not installed Manufacturer's name Peerless-FMC Model number 4664 HP 100 Volts _____ Length of drop pipe 230 ft. capacity 1300 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
16 Remarks: elevation Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley Good well. Mrs. Tegeler is owner Wesley Warner Eminence Rt. Garden City, Ks. 67846 is tenant				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Minter-Wilson Drilling Co. 208 Business name _____ License No. _____ Address Box 493 Garden City, Ks. Signed M. L. Decker Date 6-20-75 Authorized representative		

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5

WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

Lesley Werner
Gray County
-26-75

Locations: East of Garden City from the phone line road
go 8½ Miles East on North side of road S&N 14-24-30

Test #1 Static Water Level 120'

0	3	Top soil
3	87	Brown Sandy Clay
87	95	Fine to Medium Sand & Coarse Gravel Tight
95	103	Brown Sandy Clay
103	124	Fine to Medium Sand & Gravel Loose
124	142	Brown Sandy Clay
142	160	Brown white Clay white Rock
160	172	Fine to medium Sand Gravel Streaked with Clay
172	181	Fine to medium Sand & Gravel good Loose
181	185	Fine to medium Sand & Gravel Streak of clay loose
185	200	Fine to medium Sand & Gravel Loose
200	215	Fine to medium Sand & Gravel Mixed white rock good Loose
215	232	Fine to medium Sand & Gravel Coarse white rock Loose
232	245	Yellow Shale

XXX

To 240'

20' Screen