

WATER WELL RECORD Form WWD-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction : Section Number : Township Number : Range Number
 COUNTY: 035 GRAY NW 1/4 NW 1/4 SW 1/4 : 31 : T 24 S : R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3 MILES NORTH AND 1 MILE EAST OF PIERCEVILLE

2 WATER WELL OWNER: STEVE IRSIK & SONS, INC.
 RR#, St. Address, Box #: RT. 1, P.O. BOX 83 Board of Agriculture, Division of Water Resources

City, State, ZIP code : INGALLS, KS 67853 Application Number:

3 LOCATE WELL'S LOCATION WITH 4 DEPTH OF COMPLETED WELL 285 ELEVATION: 0
 AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 142 ft. 2. 0 ft. 3. 0 ft.
 / \ / / / / WELL'S STATIC WATER LEVEL 142 ft. below land surface measured on mo/day/yr 10/10/91
 1 NW NE / / / / Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 M / / / / Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 e W X E Bore Hole Diameter 9.875 in. to 285 ft., and in. to 0 ft.
 / / / / WELL WATER TO BE USED AS: 01 DOMESTIC
 --- SW SE --- / / / / Was a chemical/bacteriological sample submitted to department? No ;
 / / / / If yes, mo/day/yr sample was submitted Water well disinfected? Yes
 --- / / / /

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 285 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 225 ft. to 285 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 30 ft. to 285 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 10 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHEAST How many feet? 15

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	7	01 CLAY			
7	15	04 SANDY CLAY 05 SAND			
15	40	31 CALICHE			
40	47	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
47	64	23 SANDSTONE 01 CLAY 20 LIMESTONE			
64	123	04 SANDY CLAY 05 SAND			
123	150	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
150	169	04 SANDY CLAY 07 FINE SAND 20 LIMESTONE			
169	174	04 SANDY CLAY 07 FINE SAND 08 MEDIUM SAND			
174	188	05 SAND 13 FINE GRAVEL 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/11/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/13/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas R. Henkle*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
| COUNTY: 035 GRAY | NW 1/4 NW 1/4 SW 1/4 | 31 | T 24 S | R 30 W

2 WATER WELL OWNER: STEVE IRSIK & SONS, INC.
| RR#, St. Address, Box # : RT. 1, P.O. BOX 83

Board of Agriculture, Division of Water Resources

3 City, State, ZIP code : INGALLS, KS 67853-

Application Number:

FROM	TO	LITHOLOGIC LOG
188	194	04 SANDY CLAY
194	203	05 SAND 13 FINE GRAVEL 28 ROCK
203	214	07 FINE SAND 08 MEDIUM SAND 01 CLAY
214	222	05 SAND 28 ROCK 01 CLAY
222	226	04 SANDY CLAY
226	241	05 SAND 11 GRAVEL 28 ROCK
241	252	05 SAND 13 FINE GRAVEL 30 ROCK & CLAY
252	266	05 SAND 19 SHALE
266	283	05 SAND 13 FINE GRAVEL 30 ROCK & CLAY
283	286	19 SHALE
286	290	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/11/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/13/92 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Daughan R. Henkle