

WATER WELL RECORD Form WWC-5 KSA 82a-1212

| | | | | |
|---|----------------------------------|----------------------|---------------------------|------------------------|
| 1 LOCATION OF WATER WELL: COUNTY: 035 GRAY | Fraction NE 1/4 SE 1/4 SW 1/4 | Section Number 36 | Township Number T 24 S | Range Number R 30 W |
|---|----------------------------------|----------------------|---------------------------|------------------------|

Distance and direction from nearest town or city street address of well if located within city?
FROM CHARLESTON; APPX 3 MILES NORTH

2 WATER WELL OWNER: STEVE IRSIK JR
RR#, St. Address, Box #: 5405 6TH ROAD
City, State, ZIP code : INGALLS, KS 67853-9044

Board of Agriculture, Division of Water Resources
Application Number: 22490

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 305 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 195 ft. below land surface measured on mo/day/yr 08/11/04
Pump testdata: Well water was 243 ft. after 4 hours pumping 298 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 305 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL

CASING JOINTS: WELDED

Blank casing diameter 16 in. to 305 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 235 ft. to 285 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 305 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? NORTHWEST

How many feet? 103

| FROM | TO | LITHOLOGIC LOG | FROM | TO | PLUGGING INTERVALS |
|------|-----|--------------------------------------|------|----|--------------------|
| 0 | 2 | 02 SILT | | | |
| 2 | 20 | 01 CLAY 31 CALICHE 05 SAND | | | |
| 20 | 60 | 01 CLAY 36 GYP ROCK | | | |
| 60 | 73 | 04 SANDY CLAY 07 FINE SAND | | | |
| 73 | 80 | 05 SAND 13 FINE GRAVEL 14 MED GRAVEL | | | |
| 80 | 97 | 01 CLAY 05 SAND | | | |
| 97 | 135 | 05 SAND 13 FINE GRAVEL 01 CLAY | | | |
| 135 | 140 | 01 CLAY | | | |
| 140 | 144 | 05 SAND 13 FINE GRAVEL | | | |
| 144 | 183 | 01 CLAY 20 LIMESTONE 05 SAND | | | |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/06/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/20/04 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Benny Leichtfuss*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

| | | | | |
|---|----------------------------------|----------------------|---------------------------|------------------------|
| 1 LOCATION OF WATER WELL: COUNTY: 035 GRAY | Fraction NE 1/4 SE 1/4 SW 1/4 | Section Number 36 | Township Number T 24 S | Range Number R 30 W |
|---|----------------------------------|----------------------|---------------------------|------------------------|

2 WATER WELL OWNER: STEVE IRSIK JR

RR#, St. Address, Box #: 5405 6TH ROAD

City, State, ZIP code : INGALLS, KS 67853-9044

Board of Agriculture, Division of Water Resources

Application Number: 22490

| FROM | TO | LITHOLOGIC LOG |
|------|-----|--------------------------------|
| 183 | 208 | 05 SAND 13 FINE GRAVEL 28 ROCK |
| 208 | 233 | 01 CLAY |
| 233 | 251 | 05 SAND |
| 251 | 260 | 05 SAND 01 CLAY |
| 260 | 285 | 05 SAND 13 FINE GRAVEL 28 ROCK |
| 285 | 289 | 01 CLAY |
| 289 | 310 | 19 SHALE |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/06/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 under the business name of HENKLE DRILLING & SUPPLY

This Water Well Record was completed on (mo/day/yr) 10/20/04

by (signature)

