

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction SW 1/4 SE 1/4 SE 1/4	Section Number 12	Township Number T 24 S	Range Number R 31 W
---	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM PIERCEVILLE; APPX 6 MILES NORTH

2 WATER WELL OWNER: HAROLD BRANDT
RR#, St. Address, Box # : 10110 N. MENNONITE ROAD Board of Agriculture, Division of Water Resources
City, State, ZIP code : GARDEN CITY, KS 67846-9140 Application Number: 17319

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

1	---	NW	---	NE	---
M	---		---		---
i	W				E
l	---		---		---
e	---	SW	---	SE	---
\ /	---		---		---

4 DEPTH OF COMPLETED WELL 265 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 178 ft. below land surface measured on mo/day/yr 05/24/06
Pump test data: Well water was 226 ft. after 4 hours pumping 448 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 265 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
Blank casing diameter 16 in. to 265 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 206 ft. to 246 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 265 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: 14 ABAND. WELL
Direction from well? WEST How many feet? 100

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	22	01 CLAY			
22	47	01 CLAY			
47	85	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL			
85	102	01 CLAY			
102	110	07 FINE SAND 08 MEDIUM SAND			
110	111	01 CLAY			
111	120	07 FINE SAND 08 MEDIUM SAND			
120	150	01 CLAY 05 SAND			
150	156	08 MEDIUM SAND 09 COARSE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/22/06 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction SW 1/4 SE 1/4 SE 1/4	Section Number 12	Township Number T 24 S	Range Number R 31 W
---	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP code :	HAROLD BRANDT 10110 N. MENNONITE ROAD GARDEN CITY, KS 67846-9140	Board of Agriculture, Division of Water Resources Application Number: 17319
---	--	--

FROM	TO	LITHOLOGIC LOG
156	179	01 CLAY
179	185	01 CLAY
185	189	01 CLAY
189	193	09 COARSE SAND 11 GRAVEL
193	194	01 CLAY
194	197	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL
197	206	01 CLAY
206	216	05 SAND
216	222	08 MEDIUM SAND 09 COARSE SAND 13 FINE GRAVEL
222	237	05 SAND 11 GRAVEL
237	241	01 CLAY
241	245	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL
245	249	31 CALICHE
249	250	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/22/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06 under the business name of HENKLE DRILLING & SUPPLY by (signature) 