

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Finney		SW ¼ SW ¼ SW ¼		16		T 24 S		R 32 EW	
Distance and direction from nearest town or city street address of well if located within city? 156 N Campus Dr, Garden City									
2 WATER WELL OWNER: U Pump It Kansas, Inc.									
RR#, St. Address, Box # : 504 E Fulton St #B					Board of Agriculture, Division of Water Resources				
City, State, ZIP Code : Garden City, Kansas 67846					Application Number:				
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:			4 DEPTH OF COMPLETED WELL: 120 ft ELEVATION: 2825.24						
			Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.						
			WELL'S STATIC WATER LEVEL 74.67 ft. below land surface measured on mo/day/yr 11/19/2015						
			Pump test data: Well water was NA ft. after hours pumping gpm						
			Est. Yield NA gpm: Well water was ft. after hours pumping gpm						
			Bore Hole Diameter 8.5 in. to 123 ft. and in. to ft.						
WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well									
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)									
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well									
Was a chemical/bacteriological sample submitted to Department? Yes.....No ☒ ; If yes, mo/day/yr sample was submitted									
Water Well Disinfection? Yes No ☒									
5 TYPE OF BLANK CASING USED:									
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped									
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded									
7 Fiberglass Threaded. ☒									
Blank casing diameter 4 in. to 55 ft. Dia in. to ft. Dia in. to ft.									
Casing height above land surface 4.8 in., weight lbs./ft. Wall thickness or gauge No. Sch. 80									
TYPE OF SCREEN OR PERFORATION MATERIAL									
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement									
2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)									
9 ABS 12 None used (open hole)									
SCREEN OR PERFORATION OPENINGS ARE:									
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)									
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes									
7 Torch cut 10 Other (specify)									
SCREEN-PERFORATED INTERVALS: From 55 ft. to 120 ft. From ft. to ft.									
From ft. to ft. From ft. to ft.									
GRAVEL PACK INTERVALS: From 52 ft. to 123 ft. From ft. to ft.									
From ft. to ft. From ft. to ft.									
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Concrete									
Grout intervals: From 0 ft. to 2 ft. From 2 ft. to 54 ft. From ft. to ft.									
What is the nearest source of possible contamination:									
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well									
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well									
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)									
13 Insecticide storage									
Direction from well? How many feet?									
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS									
0	0.5	Concrete,	112	123	Clay, sandy w/sand lenses, Lt. Brown				
0.5	7	Clay, silty w/occ. sand, Lt. Brown							
7	26	Sand, vf-c,							
26	33	Sand, f to f gravel,							
33	43	Sand, f-c w/tr. f gravel,							
43	52	Clay, sandy w/sand stringers, Lt. Gray							
52	57	Clay, v. sandy w/sand lenses, Lt. Red Brown							
57	60	Sand, f-c w/tr. f gravel,							
60	62	Sand, f-c w/f gravel,							
62	65	Sandstone, vf-m, mod.-well cmntd, Lt. Gray							
65	68	Sand, vf-c w/tr. f gravel, tr. clay,							
68	72	Sand and gravel w/lt. gray caliche stringers,							
72	80	Clay, sandy w/tr. f gravel, Lt. Red Brown			MW20, Flushmount				
80	101	Sand, f-c w/tr. f gravel,							
101	112	Clay, sandy w/sand lenses, Lt. Gray							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was 1 constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 11/18/2015 and this record is true to the best of my knowledge and belief.									
Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 12/14/2015 under the business name of GeoCore, Inc. by (signature) <i>[Signature]</i>									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.									

OFFICE USE ONLY

T

R

EW

SEC.

¼

¼

¼