

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction NE 1/4 NW 1/4 SW 1/4	Section Number 9	Township Number T 24 S	Range Number R 33 W
---	----------------------------------	---------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM HOLCOMB; APPX 1 1/2 MILE EAST

2 WATER WELL OWNER: GERARDO SANTOS
RR#, St. Address, Box # : PO BOX 406
City, State, ZIP code : DEERFIELD, KS 67838-0406
Board of Agriculture, Division of Water Resources
Application Number:

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

/ \				
1	---	NW	---	NE
M				
i	W			E
l		X		
e				
		SW		SE
\ /				

4 DEPTH OF COMPLETED WELL 320 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 73 ft. below land surface measured on mo/day/yr 04/17/05
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 10 in. to 320 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: OTHER - Certi-Lok
Blank casing diameter 5 in. to 320 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS:	From 220 ft. to 240 ft.,	From 300 ft. to 320 ft.
	From 260 ft. to 280 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 25 ft. to 320 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE OBSERVED

Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	6	04 SANDY CLAY			
6	50	05 SAND 11 GRAVEL			
50	66	04 SANDY CLAY			
66	70	05 SAND 13 FINE GRAVEL			
70	155	04 SANDY CLAY			
155	170	05 SAND 13 FINE GRAVEL			
170	180	01 CLAY 20 LIMESTONE			
180	189	05 SAND			
189	200	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/19/05 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/09/05
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction 1/4 1/4 SW 1/4	Section Number 9	Township Number T 24 S	Range Number R 33 W
---	----------------------------	---------------------	---------------------------	------------------------

2 WATER WELL OWNER: GERARDO SANTOS

RR#, St. Address, Box # : PO BOX 406

City, State, ZIP code : DEERFIELD, KS 67838-0406

Board of Agriculture, Division of Water Resources

Application Number:

FROM	TO	LITHOLOGIC LOG
200	209	05 SAND
209	216	04 SANDY CLAY
216	229	05 SAND 13 FINE GRAVEL
229	230	04 SANDY CLAY
230	244	05 SAND 13 FINE GRAVEL
244	260	04 SANDY CLAY 05 SAND
260	272	05 SAND 01 CLAY
272	301	04 SANDY CLAY 05 SAND
301	320	05 SAND 01 CLAY
320	337	04 SANDY CLAY 05 SAND
337	347	31 CALICHE 20 LIMESTONE
347	355	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/19/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/09/05 under the business name of HENKLE DRILLING & SUPPLY by (signature) *B. J. Reichert*