

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction SE 1/4 NW 1/4 SE 1/4	Section Number 07	Township Number T 24 S	Range Number R 33 W
---	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM HOLCOMB; APPX 1/8 MILE SOUTH

2 WATER WELL OWNER: RICHARD WEBDELL
RR#, St. Address, Box #: PO BOX 108
City, State, ZIP code: HOLCOMB, KS 67851-0108
Board of Agriculture, Division of Water Resources
Application Number: FI-128

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 268 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 70 ft. below land surface measured on mo/day/yr 05/13/06
Pump test data: Well water was 94 ft. after 4 hours pumping 800 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 268 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
Blank casing diameter 16 in. to 268 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 157 ft. to 197 ft.,	From 0 ft. to 0 ft.
	From 233 ft. to 263 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 70 ft.,	From 0 ft. to 0 ft.
	From 70 ft. to 268 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 70 ft. to 90 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: 14 ABAND. WELL
Direction from well? NORTH How many feet? 264

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	4	04 SANDY CLAY			
4	36	05 SAND 11 GRAVEL			
36	74	01 CLAY 20 LIMESTONE			
74	83	01 CLAY 05 SAND			
83	104	04 SANDY CLAY 05 SAND			
104	116	05 SAND 01 CLAY			
116	134	04 SANDY CLAY			
134	140	01 CLAY			
140	147	07 FINE SAND 08 MEDIUM SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/09/06 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/23/06
under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	SE 1/4 NW 1/4 SE 1/4	07	T 24 S	R 33 W

2 WATER WELL OWNER:		
RICHARD WEBDELL		
RR#, St. Address, Box # :	PO BOX 108	Board of Agriculture, Division of Water Resources
City, State, ZIP code :	HOLCOMB, KS 67851-0108	Application Number: FI-128

FROM	TO	LITHOLOGIC LOG
147	156	04 SANDY CLAY 05 SAND
156	166	05 SAND 13 FINE GRAVEL
166	172	04 SANDY CLAY 05 SAND
172	197	05 SAND 13 FINE GRAVEL
197	230	04 SANDY CLAY 05 SAND
230	249	05 SAND
249	252	04 SANDY CLAY
252	263	05 SAND
263	277	31 CALICHE
277	280	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/09/06 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/23/06
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Richmond*