

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No.

1 LOCATION OF WATER WELL: County: <u>Finney</u>		Fraction <u>SW 1/4 SW 1/4 SE 1/4</u>	Section Number <u>9</u>	Township Number <u>T 24 S</u>	Range Number <u>R 33 E/W</u>
Distance and direction from nearest town or city street address of well if located within city?			Global Positioning Systems (decimal degrees, min. of 4 digits) Latitude: _____ Longitude: _____ Elevation: _____ Datum: _____ Data Collection Method: _____		
2 WATER WELL OWNER: <u>Richard Webdell</u> RR#, St. Address, Box # : <u>22433 Railroad Ave.</u> City, State, ZIP Code : <u>Garden City, KS 67846</u>					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: N NW NE SW SE X S		4 DEPTH OF COMPLETED WELL <u>340</u> ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL..... <u>122</u> ft. below land surface measured on mo/day/yr. <u>7-12-06</u> Pump test data: Well water was..... ft. after..... hours pumping..... gpm Est. Yield..... <u>150</u> gpm: Well water was..... ft. after..... hours pumping..... gpm WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well ☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No ☒; If yes, mo/day/yr Sample was submitted..... Water well disinfected? Yes ☒ No			
5 TYPE OF CASING USED:					
1 Steel 3 RMP (SR)		5 Wrought Iron 8 Concrete tile		CASING JOINTS: Glued ☒ Clamped.....	
☒ PVC 4 ABS		6 Asbestos-Cement 9 Other (specify below)		Welded.....	
7 Fiberglass				Threaded.....	
Blank casing diameter <u>10</u> in. to <u>340</u> ft., Diameter..... in. to ft., Diameter..... in. to ft.					
Casing height above land surface..... <u>12</u> in., Weight..... lbs./ft. Wall thickness or gauge No. <u>200 p5.1</u>					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless Steel 5 Fiberglass ☒ PVC 9 ABS		11 Other (Specify)			
2 Brass 4 Galvanized Steel 6 Concrete tile 8 RM (SR) 10 Asbestos-Cement		12 None used (open hole)			
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Guazed wrapped 7 Torch cut 9 Drilled holes 11 None (open hole)					
2 Louvered shutter 4 Key punched 6 Wire wrapped ☒ Saw Cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From..... <u>313</u> ft. to <u>340</u> ft., From..... ft. to ft.					
From..... ft. to ft., From..... ft. to ft.					
GRAVEL PACK INTERVALS: From..... <u>74</u> ft. to <u>150</u> ft., From..... ft. to ft.					
From..... <u>160</u> ft. to <u>340</u> ft., From..... ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ☒ Bentonite 4 Other					
Grout Intervals: From..... <u>5</u> ft. to <u>74</u> ft., From..... <u>150</u> ft. to <u>160</u> ft., From..... ft. to ft.					
What is the nearest source of possible contamination:					
☒ Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 13 Insecticide Storage 16 Other (specify below)					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 14 Abandoned water well					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer Storage 15 Oil well/gas well					
Direction from well? How many feet? <u>100</u>					
FROM		TO		LITHOLOGIC LOG	
FROM		TO		PLUGGING INTERVALS	
0		2		top soil	
2		9		brown clay	
9		54		coarse sand - coarse gravel	
54		149		brown clay	
149		153		medium to coarse sand	
153		163		brown clay	
163		170		medium to coarse sand	
170		184		brown clay, sand streaks	
184		220		medium to coarse sand, small gravel, (clean loose)	
220		221		brown clay	
221		227		med. to coarse sand, small gravel, loose, (clean)	
227		273		brown + white clay	
273		283		fine to medium sand	
283		297		fine to medium sand, few clay streaks	
297		309		brown + yellow clay, trace of med sand	
309		317		coarse sand, small gravel, clean	
317		318		brown clay	
318		337		coarse sand, small gravel, clean	
337		342		brown + yellow clay	
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>7-12-06</u> ... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>532</u> ... This Water Well Record was completed on (mo/day/year) <u>7-24-06</u> ... under the business name of <u>Midwest Well & Pump Inc.</u> by (signature) <u>John Sunkup</u>					
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each <u>constructed</u> well. Visit us at http://www.kdhe.state.ks.us/geo/waterwells .					