

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	NW 1/4 NW 1/4 SE 1/4	04	T 24 S	R 33 W

Distance and direction from nearest town or city street address of well if located within city?

FROM GARDEN CITY; APPX 2 MILES EAST

2 WATER WELL OWNER:	HOWARD BRAUN	
RR#, St. Address, Box # :	1402 MELS DRIVE	Board of Agriculture, Division of Water Resources
City, State, ZIP code :	GARDEN CITY, KS 67846-3364	Application Number: FI-118

3 LOCATE WELL'S LOCATION WITH	4 DEPTH OF COMPLETED WELL	305 ELEVATION:	0
AN "X" IN SECTION BOX:	Depth(s) Groundwater Encountered	1.	0 ft. 2. 0 ft. 3. 0 ft.
/ \	WELL'S STATIC WATER LEVEL	84 ft. below land surface measured on mo/day/yr	06/19/06
1	Pump test data: Well water was	165 ft. after	4 hours pumping 1200 gpm
M	Estimated Yield	0 gpm: Well water was	0 ft. after 0 hours pumping 0 gpm
i W	Bore Hole Diameter	24 in. to 305 ft., and	in. to 0 ft.
l	WELL WATER TO BE USED AS:	02 IRRIGATION	
e	Was a chemical/bacteriological sample submitted to department?	No ;	
\ /	If yes, mo/day/yr sample was submitted		Water well disinfected? Yes

5 TYPE OF BLANK CASING USED:	01 STEEL	CASING JOINTS:	WELDED
Blank casing diameter	16 in. to 305 ft., Dia	in. to 0 ft., Dia	in. to 0 ft.
Casing height above land surface	12 in., weight	42 lbs/ft. Wall thickness or gauge No. .25	
TYPE OF SCREEN OR PERFORATION MATERIAL:	01 STEEL		
SCREEN OR PERFORATION OPENINGS ARE:	01 CONT. SLOT		

SCREEN PERFORATED INTERVALS:	From 180 ft. to 300 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 305 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL	03 BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination:	14 ABAND. WELL
Direction from well?	SOUTHWEST
	How many feet? 97

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	10	01 CLAY 31 CALICHE			
10	30	05 SAND 11 GRAVEL			
30	42	01 CLAY 31 CALICHE			
42	54	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
54	91	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
91	103	01 CLAY 20 LIMESTONE			
103	113	01 CLAY			
113	126	05 SAND 11 GRAVEL 28 ROCK			
126	145	05 SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/15/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/09/06 under the business name of HENKLE DRILLING & SUPPLY by (signature) /

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	NW 1/4 NW 1/4 SE 1/4	04	T 24 S	R 33 W

2 WATER WELL OWNER:	HOWARD BRAUN	
RR#, St. Address, Box # :	1402 MELS DRIVE	Board of Agriculture, Division of Water Resources
City, State, ZIP code :	GARDEN CITY, KS 67846-3364	Application Number: FI-118

FROM	TO	LITHOLOGIC LOG
145	168	05 SAND 13 FINE GRAVEL
168	174	01 CLAY
174	194	05 SAND 13 FINE GRAVEL
194	220	01 CLAY 20 LIMESTONE 05 SAND
220	238	07 FINE SAND 01 CLAY
238	251	01 CLAY
251	267	07 FINE SAND 01 CLAY
267	285	05 SAND 13 FINE GRAVEL 01 CLAY
285	300	05 SAND 11 GRAVEL 28 ROCK
300	306	31 CALICHE 20 LIMESTONE
306	320	19 SHALE 20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/15/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/09/06 under the business name of HENKLE DRILLING & SUPPLY by (signature) 
