

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	NE 1/4 NW 1/4 SW 1/4	29	T 24 S	R 33 W

Distance and direction from nearest town or city street address of well if located within city?
FROM HOLCOMB; APPX 3 MILES SOUTH

2 WATER WELL OWNER: **SUNFLOWER ELECTRIC POWER**
 RR#, St. Address, Box #: **PO BOX 430** Board of Agriculture, Division of Water Resources
 City, State, ZIP code: **HOLCOMB, KS 67851-0430** Application Number: **28415**

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
4	5	6	7
8	9	10	11
12	13	14	15

WELL'S STATIC WATER LEVEL 0 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 36 in. to 403 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 04 INDUSTRIAL
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 403 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 63 lbs/ft. Wall thickness or gauge No. .375
 TYPE OF SCREEN OR PERFORATION MATERIAL: 03 STAINLESS ST
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 230 ft. to 300 ft., From 0 ft. to 0 ft.
 From 336 ft. to 396 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 75 ft. to 185 ft., From 0 ft. to 0 ft.
 From 215 ft. to 402 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 Cement 03 Bentonite
 Grout Intervals: From 0 ft. to 75 ft., From 185 ft. to 215 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? EAST How many feet? 219

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	8	07 FINE SAND			
8	42	05 SAND			
42	63	05 SAND 11 GRAVEL			
63	74	04 SANDY CLAY			
74	88	05 SAND 13 FINE GRAVEL 01 CLAY			
88	105	04 SANDY CLAY			
105	115	05 SAND			
115	120	04 SANDY CLAY			
120	136	05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/19/07 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/24/07
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	NE 1/4 NW 1/4 SW 1/4	29	T 24 S	R 33 W

2 WATER WELL OWNER: **SUNFLOWER ELECTRIC POWER**
RR#, St. Address, Box # : **PO BOX 430**
City, State, ZIP code : **HOLCOMB, KS 67851-0430**

Board of Agriculture, Division of Water Resources
Application Number: **28415**

FROM	TO	LITHOLOGIC LOG
136	145	04 SANDY CLAY 01 CLAY
145	229	01 CLAY
229	248	07 FINE SAND 08 MEDIUM SAND 01 CLAY
248	276	04 SANDY CLAY 05 SAND
276	285	05 SAND
285	335	04 SANDY CLAY 05 SAND
335	396	05 SAND
396	400	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) **06/19/07** and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. **145** This Water Well Record was completed on (mo/day/yr) **08/24/07**
under the business name of **HENKLE DRILLING & SUPPLY** by (signature)

Brian J. Leckman