

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	NE 1/4 NE 1/4 NW 1/4	07	T 24 S	R 33 W

Distance and direction from nearest town or city street address of well if located within city?
FROM HOLCOMB; APPX 1/8 MILE EAST

2 WATER WELL OWNER: **CITY OF HOLCOMB**
 RR#, St. Address, Box # : **PO BOX 69** Board of Agriculture, Division of Water Resources
 City, State, ZIP code : **HOLCOMB, KS 67851-** Application Number: **21119**

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 301 ELEVATION: 0																																																
<table border="1"> <tr> <td>/ \</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>1</td> <td>---</td> <td>NW</td> <td>---</td> <td>NE</td> <td>---</td> </tr> <tr> <td>M</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>i</td> <td>W</td> <td>---</td> <td>---</td> <td>---</td> <td>E</td> </tr> <tr> <td>l</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>e</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>---</td> <td>SW</td> <td>---</td> <td>SE</td> <td>---</td> </tr> <tr> <td>\ /</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	/ \						1	---	NW	---	NE	---	M						i	W	---	---	---	E	l						e							---	SW	---	SE	---	\ /						WELL'S STATIC WATER LEVEL 92 ft. below land surface measured on mo/day/yr 09/25/07 Pump test data: Well water was 126 ft. after 8 hours pumping 800 gpm Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 30 in. to 301 ft., and in. to 0 ft. WELL WATER TO BE USED AS: 05 PUB. WTR SUP Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes
/ \																																																	
1	---	NW	---	NE	---																																												
M																																																	
i	W	---	---	---	E																																												
l																																																	
e																																																	
	---	SW	---	SE	---																																												
\ /																																																	

5 TYPE OF BLANK CASING USED: **01 STEEL** CASING JOINTS: **WELDED**
 Blank casing diameter **16** in. to **301** ft., Dia in. to **0** ft., Dia in. to **0** ft.
 Casing height above land surface **12** in., weight **63** lbs/ft. Wall thickness or gauge No. **.375**
 TYPE OF SCREEN OR PERFORATION MATERIAL: **03 STAINLESS ST**
 SCREEN OR PERFORATION OPENINGS ARE: **01 CONT. SLOT**

SCREEN PERFORATED INTERVALS:	From 174 ft. to 234 ft., From 0 ft. to 0 ft.
	From 254 ft. to 296 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 160 ft. to 240 ft., From 0 ft. to 0 ft.
	From 240 ft. to 301 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL **02 CEMENT GROUT** *Barfante*
 Grout Intervals: From **0** ft. to **117** ft., From **117** ft. to **160** ft., From **0** ft. to **0** ft.
 What is the nearest source of possible contamination: **WATER WELL**
 Direction from well? **NORTHWEST** How many feet? **95**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	11	04 SANDY CLAY			
11	17	05 SAND 11 GRAVEL			
17	18	01 CLAY			
18	37	05 SAND 11 GRAVEL			
37	86	04 SANDY CLAY 20 LIMESTONE			
86	94	05 SAND			
94	112	04 SANDY CLAY 05 SAND			
112	117	05 SAND			
117	143	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) **09/15/07** and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. **145** This Water Well Record was completed on (mo/day/yr) **11/14/07**
 under the business name of **HENKLE DRILLING & SUPPLY** by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	NE 1/4 NE 1/4 NW 1/4	07	T 24 S	R 33 W

2 WATER WELL OWNER: CITY OF HOLCOMB

RR#, St. Address, Box # : PO BOX 69

Board of Agriculture, Division of Water Resources

City, State, ZIP code : HOLCOMB, KS 67851-

Application Number: 21119

FROM	TO	LITHOLOGIC LOG
143	174	04 SANDY CLAY 20 LIMESTONE
174	234	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
234	238	04 SANDY CLAY 05 SAND
238	269	05 SAND
269	276	07 FINE SAND 01 CLAY
276	296	05 SAND 08 MEDIUM SAND
296	301	20 LIMESTONE 31 CALICHE
301	310	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/15/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 11/14/07

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruce J. Kerhman