

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 028 FINNEY NW 1/4 NW 1/4 NW 1/4 13 T 24 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM GARDEN CITY; APPX 1 MILE WEST

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT  
 RR#, St. Address, Box # : PO BOX 1078 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code : GARDEN CITY, KS 67846-1078 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 260 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 0 ft. below land surface measured on mo/day/yr  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 6 in. to 260 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 10 MONITORING  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 2 in. to 260 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 1 lbs/ft. Wall thickness or gauge No. .218  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT  
 SCREEN PERFORATED INTERVALS: From 240 ft. to 260 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 220 ft. to 260 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 20 ft. to 220 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	3	04 SANDY CLAY			
3	41	05 SAND 11 GRAVEL			
41	64	04 SANDY CLAY			
64	77	07 FINE SAND 08 MEDIUM SAND			
77	79	04 SANDY CLAY			
79	86	19 SHALE			
86	114	01 CLAY			
114	162	04 SANDY CLAY 05 SAND			
162	180	05 SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/05/07 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/15/07  
 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Baumgardner*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	NW 1/4 NW 1/4 NW 1/4	13	T 24 S	R 33 W

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT

RR#, St. Address, Box # : PO BOX 1078

Board of Agriculture, Division of Water Resources

City, State, ZIP code : GARDEN CITY, KS 67846-1078

Application Number:

FROM	TO	LITHOLOGIC LOG
180	207	04 SANDY CLAY 05 SAND
207	212	05 SAND
212	219	04 SANDY CLAY 05 SAND
219	232	05 SAND
232	251	04 SANDY CLAY 05 SAND
251	260	07 FINE SAND 08 MEDIUM SAND 01 CLAY
260	315	04 SANDY CLAY
315	320	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/05/07 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/15/07  
under the business name of HENKLE DRILLING & SUPPLY by (signature)