

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 028 FINNEY NE 1/4 SE 1/4 NW 1/4 13 T 24 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?

FROM GARDEN CITY; APPX 1/4 MILE WEST

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT

RR#, St. Address, Box # : PO BOX 1078

Board of Agriculture, Division of Water Resources

City, State, ZIP code : GARDEN CITY, KS 67846-1078

Application Number:

3 LOCATE WELL'S LOCATION WITH

4 DEPTH OF COMPLETED WELL 310 ELEVATION: 0

AN "X" IN SECTION BOX:

Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \

WELL'S STATIC WATER LEVEL 117 ft. below land surface measured on mo/day/yr 08/27/07

Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

1

NW

NE

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

M

W

E

Bore Hole Diameter 6 in. to 310 ft., and in. to 0 ft.

1

WELL WATER TO BE USED AS: 10 MONITORING

e

SW

SE

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted

Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC

CASING JOINTS: GLUED

Blank casing diameter 2 in. to 310 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 1 lbs/ft. Wall thickness or gauge No. .218

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS:

From 290 ft. to 310 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS:

From 270 ft. to 310 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT

03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 20 ft. to 270 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE OBSERVED

Direction from well?

How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	4	04 SANDY CLAY			
4	42	05 SAND 11 GRAVEL			
42	83	04 SANDY CLAY 05 SAND			
83	88	07 FINE SAND			
88	94	31 CALICHE			
94	97	19 SHALE			
97	157	01 CLAY			
157	168	05 SAND			
168	176	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/28/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 10/15/07

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	NE 1/4 SW 1/4 NW 1/4	13	T 24 S	R 33 W

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT  
RR#, St. Address, Box # : PO BOX 1078  
City, State, ZIP code : GARDEN CITY, KS 67846-1078

Board of Agriculture, Division of Water Resources  
Application Number:

FROM	TO	LITHOLOGIC LOG
176	197	04 SANDY CLAY 13 FINE GRAVEL
197	216	04 SANDY CLAY 05 SAND
216	236	05 SAND
236	249	04 SANDY CLAY
249	310	07 FINE SAND 08 MEDIUM SAND 01 CLAY
310	316	31 CALICHE
316	320	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/28/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 10/15/07

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

*Bruce J. Reckman*