

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 028 FINNEY NE 1/4 SE 1/4 NW 1/4 13 T 24 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?

FROM GARDEN CITY; APPX 1/4 MILE WEST

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT

RR#, St. Address, Box # : PO BOX 1078

Board of Agriculture, Division of Water Resources

City, State, ZIP code : GARDEN CITY, KS 67846-1078

Application Number:

3 LOCATE WELL'S LOCATION WITH

4 DEPTH OF COMPLETED WELL 89 ELEVATION: 0

AN "X" IN SECTION BOX:

Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \ WELL'S STATIC WATER LEVEL 34 ft. below land surface measured on mo/day/yr 08/24/07

Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

1 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

M Bore Hole Diameter 6 in. to 89 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 10 MONITORING

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC

CASING JOINTS: GLUED

Blank casing diameter 2 in. to 89 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 1 lbs/ft. Wall thickness or gauge No. .218

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 69 ft. to 89 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 59 ft. to 89 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT

03 Bentonite

Grout Intervals: From 0 ft. to 20 ft., From 20 ft. to 59 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE OBSERVED

Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	4	04 SANDY CLAY			
4	46	05 SAND 11 GRAVEL			
46	69	04 SANDY CLAY			
69	71	07 FINE SAND 08 MEDIUM SAND			
71	76	04 SANDY CLAY			
76	89	05 SAND			
89	96	01 CLAY			
96	100	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/25/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 10/15/07

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

*Bruce R. Smith*