

**CORRECTION(S) TO WATER WELL RECORD (WWC-5)**

(to rectify lacking or incorrect information)

Location listed as:

Section-Township-Range: 13-245-3.5W

Fraction (  $\frac{1}{4}$   $\frac{1}{4}$   $\frac{1}{4}$  ): NW NE NW

County: Finney

Location changed to:

13-245-33W

NW NE NW

Other changes: Initial statements: \_\_\_\_\_

Changed to: \_\_\_\_\_

Comments: \_\_\_\_\_

verification method: Written & legal descriptions, other well records for  
same owner at same location, position on plat map, and  
mapping tool on KGS website. initials: DRG date: 3/17/2008

submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726

to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 028 FINNEY NW 1/4 NE 1/4 NW 1/4 13 T 24 S R 35 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM GARDEN CITY; APPX 1/4 MILE WEST

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT  
 RR#, St. Address, Box #: PP BOX 1078 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: GARDEN CITY, KS 67846-1078 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 320 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 / \ X  
 1 --- NW --- NE ---  
 M  
 i W --- E Bore Hole Diameter 6 in. to 320 ft., and in. to 0 ft.  
 l  
 e --- SW --- SE  
 \ /  
 ---  
 WELL'S STATIC WATER LEVEL 0 ft. below land surface measured on mo/day/yr  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 WELL WATER TO BE USED AS: 10 MONITORING  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 2 in. to 320 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 1 lbs/ft. Wall thickness or gauge No. .218  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT  
 SCREEN PERFORATED INTERVALS: From 300 ft. to 320 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 280 ft. to 320 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 20 ft. to 280 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	5	04 SANDY CLAY			
5	42	05 SAND 11 GRAVEL			
42	74	04 SANDY CLAY			
74	75	SHALE			
75	160	01 CLAY			
160	172	04 SANDY CLAY 05 SAND			
172	209	05 SAND 13 FINE GRAVEL 01 CLAY			
209	220	04 SANDY CLAY			
220	227	05 SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/30/07 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/15/07  
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	NW 1/4 NE 1/4 NW 1/4	13	T 24 S	R 35 W

2 WATER WELL OWNER: WHEATLAND WATER TREATMENT  
RR#, St. Address, Box # : PP BOX 1078  
City, State, ZIP code : GARDEN CITY, KS 67846-1078

Board of Agriculture, Division of Water Resources  
Application Number:

FROM	TO	LITHOLOGIC LOG
227	232	04 SANDY CLAY
232	245	04 SANDY CLAY 13 FINE GRAVEL
245	305	04 SANDY CLAY 05 SAND
305	310	07 FINE SAND 08 MEDIUM SAND
310	317	04 SANDY CLAY 05 SAND
317	320	07 FINE SAND 08 MEDIUM SAND
320	326	31 CALICHE
326	330	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/30/07 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/15/07  
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Brian R. Reith*