

## WATER WELL RECORD

## Form WWC-5

Division of Water Resources App. No. 

<b>1 LOCATION OF WATER WELL:</b> County: <b>Stevens</b>		Fraction $\frac{1}{4}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$ NE $\frac{1}{4}$	Section Number <b>5</b>	Township No. <b>T 34 S</b>	Range Number <b>R 35</b> <input type="checkbox"/> E <input checked="" type="checkbox"/> W																
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here <input type="checkbox"/> <b>11 East and 3 South of Hugoton</b>			<b>Global Positioning System (GPS) information:</b> Latitude: <b>.A</b> ..... (in decimal degrees) Longitude: ..... (in decimal degrees) Elevation: ..... Datum: <input type="checkbox"/> WGS 84, <input type="checkbox"/> NAD 83, <input type="checkbox"/> NAD 27 Collection Method: <input type="checkbox"/> GPS unit (Make/Model: .....) <input type="checkbox"/> Digital Map/Photo, <input type="checkbox"/> Topographic Map, <input type="checkbox"/> Land Survey Est. Accuracy: <input type="checkbox"/> <3 m, <input type="checkbox"/> 3-5 m, <input type="checkbox"/> 5-15 m, <input type="checkbox"/> >15 m																		
<b>2 WATER WELL OWNER:</b> <b>C.J. Skinner</b> RR#, Street Address, Box #: <b>1411 N Perdue</b> City, State, ZIP Code: <b>Liberal, KS</b>																					
<b>3 LOCATE WELL WITH AN "X" IN SECTION BOX:</b> <div style="text-align: center;">N</div> <table border="1" style="margin: auto; text-align: center;"> <tr> <td colspan="2">NW</td> <td colspan="2">NE</td> </tr> <tr> <td>W</td> <td> </td> <td> </td> <td>E</td> </tr> <tr> <td colspan="2">SW</td> <td colspan="2">SE</td> </tr> <tr> <td colspan="2">S</td> <td colspan="2"></td> </tr> </table> <div style="text-align: center;">-----1 mile-----</div>		NW		NE		W			E	SW		SE		S				<b>4 DEPTH OF COMPLETED WELL</b> <b>630</b> ..... ft. Depth(s) Groundwater Encountered (1) <b>280</b> ..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL <b>280</b> ..... ft. below land surface measured on mo/day/yr..... Pump test data: Well water was..... ft. after..... hours pumping..... gpm EST. YIELD..... gpm. Well water was..... ft. after..... hours pumping..... gpm Bore Hole Diameter <b>9 3/4</b> ..... in. to..... ft., and..... in. to..... ft. WELL WATER TO BE USED AS: <input type="checkbox"/> Public water supply <input type="checkbox"/> Geothermal <input type="checkbox"/> Injection well <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Feedlot <input type="checkbox"/> Oil field water supply <input type="checkbox"/> Dewatering <input type="checkbox"/> Other (Specify below) <input type="checkbox"/> Irrigation <input type="checkbox"/> Industrial <input type="checkbox"/> Domestic-lawn & garden <input type="checkbox"/> Monitoring well ..... Was a chemical/bacteriological sample submitted to Department? <input type="checkbox"/> Yes <input type="checkbox"/> No If yes, mo/day/yr sample was submitted..... Water well disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
NW		NE																			
W			E																		
SW		SE																			
S																					
<b>5 TYPE OF CASING USED:</b> <input type="checkbox"/> Steel <input checked="" type="checkbox"/> PVC <input type="checkbox"/> Other <b>Eagle Loc</b> ..... CASING JOINTS: <input type="checkbox"/> Glued <input type="checkbox"/> Clamped <input type="checkbox"/> Welded <input type="checkbox"/> Threaded Casing diameter <b>5</b> ..... in. to <b>630</b> ..... ft., Diameter..... in. to..... ft., Diameter..... in. to..... ft. Casing height above land surface <b>24</b> ..... in., Weight <b>SDR 17</b> ..... lbs./ft., Wall thickness or gauge No. .... TYPE OF SCREEN OR PERFORATION MATERIAL: <input type="checkbox"/> Steel <input type="checkbox"/> Stainless Steel <input checked="" type="checkbox"/> PVC <input type="checkbox"/> Other (Specify) ..... <input type="checkbox"/> Brass <input type="checkbox"/> Galvanized Steel <input type="checkbox"/> None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: <input type="checkbox"/> Continuous slot <input checked="" type="checkbox"/> Mill slot <input type="checkbox"/> Gauze wrapped <input type="checkbox"/> Torch cut <input type="checkbox"/> Drilled holes <input type="checkbox"/> None (open hole) <input type="checkbox"/> Louvered shutter <input type="checkbox"/> Key punched <input type="checkbox"/> Wire wrapped <input type="checkbox"/> Saw cut <input type="checkbox"/> Other (specify) ..... SCREEN-PERFORATED INTERVALS: From <b>450</b> ..... ft. to <b>470</b> ..... ft., From <b>490</b> ..... ft. to <b>510</b> ..... ft. From <b>550</b> ..... ft. to <b>570</b> ..... ft., From <b>610</b> ..... ft. to <b>630</b> ..... ft. GRAVEL PACK INTERVALS: From <b>30</b> ..... ft. to <b>610</b> ..... ft., From..... ft. to..... ft. From..... ft. to..... ft., From..... ft. to..... ft.																					
<b>6 GROUT MATERIAL:</b> <input type="checkbox"/> Neat cement <input type="checkbox"/> Cement grout <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Other ..... Grout Intervals: From <b>3</b> ..... ft. to <b>30</b> ..... ft., From..... ft. to..... ft., From..... ft. to..... ft. What is the nearest source of possible contamination: <input type="checkbox"/> Septic tank <input type="checkbox"/> Lateral lines <input type="checkbox"/> Pit privy <input type="checkbox"/> Livestock pens <input type="checkbox"/> Insecticide storage <input type="checkbox"/> Other (specify below) <input type="checkbox"/> Sewer lines <input type="checkbox"/> Cesspool <input type="checkbox"/> Sewage lagoon <input type="checkbox"/> Fuel storage <input checked="" type="checkbox"/> Abandoned water well <input type="checkbox"/> Watertight sewer lines <input type="checkbox"/> Seepage pit <input type="checkbox"/> Feedyard <input type="checkbox"/> Fertilizer storage <input type="checkbox"/> Oil well/gas well ..... Direction from well <b>West</b> ..... Distance from well <b>25</b> .....																					
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																
0	40	Topsoil and Clay	460	515	Sand and Little Clay																
40	100	Sandy Clay	515	520	Sand Stone																
100	120	Sand and Cliche	520	570	Sand Little Clay & Cliche																
120	160	Sandy clay and Cliche	570	580	Clay																
160	200	Clay Little Cliche and Sand	580	600	Sandy Clay																
200	220	Clay and Sand Stone	600	615	Sand																
220	300	Sandy Clay and Clay Streaks	615	622	Clay																
300	380	Sand Little Clay	622	630	Cliche																
380	440	Sand Medium	630	640	Sand and Cliche																
440	460	Sand Little Cliche																			
<b>7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:</b> This water well was <input checked="" type="checkbox"/> constructed, <input type="checkbox"/> reconstructed, or <input type="checkbox"/> plugged under my jurisdiction and was completed on (mo/day/year) <b>7/13/10</b> ..... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <b>473</b> ..... This Water Well Record was completed on (mo/day/year) <b>7/19/10</b> ..... under the business name of <b>Tyler Water Well</b> ..... by (signature) <i>[Signature]</i>																					
<b>INSTRUCTIONS:</b> Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at <a href="http://www.kdheks.gov/waterwell/index.html">http://www.kdheks.gov/waterwell/index.html</a> .																					