

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Kearny	Fraction SW 1/4 NE 1/4 NW 1/4	Section number 15	Township number T 24 S	Range number R 35 XX/W
2. Distance and direction from nearest town or city: 1W, 1/2S of Deerfield, Kansas Street address of well location if in city:				3. Owner of well: Leon Scheuerman R.R. or street: City, state, zip code: Deerfield, Kansas 67838		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>28</u> in. Completion date _____ Well depth <u>111</u> ft. <u>9-7-77</u>		
		<p>1518'E and 1023'S of the NW corner of the NW 1/4, Sec. 15, T24S, R35W, Kearny County, Kansas.</p>		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material				From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Top soil				0	8	9. Casing: Material <u>Steel</u> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>37</u> lbs./ft. Dia. <u>16</u> in. to <u>22</u> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. <u>219</u>
Fine to coarse sand fine to medium gravel				8	20	10. Screen: Manufacturer's name <u>Cook, Doerr, Foster</u> Type <u>Wirewrap, Louver, Millslot 16'</u> D/G. _____ Slot/gauze <u>1/8</u> Length <u>89</u> Set between <u>22</u> ft. and <u>111</u> ft. _____ ft. and _____ ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>5.63 mm</u>
Fine to medium sand				20	58	11. Static water level: _____ mo./day/yr. <u>19</u> ft. below land surface Date <u>7-6-77</u>
Tan clay				58	70	12. Pumping level below land surfaces: <u>Not pumped</u> _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <u>2000</u> g.p.m.
Fine to coarse sand fine gravel				70	84	13. Water sample submitted: _____ mo./day/yr. Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Date _____
Fine to medium sand				84	93	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade
Fine to coarse sand				93	111	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.
Tan sandy clay				111	123	16. Nearest source of possible contamination: <u>Unknown</u> ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Blue clay sand streaks				123	237	17. Pump: _____ Not installed Manufacturer's name <u>Layne & Bowler</u> Model number <u>12 KM</u> HP <u>45</u> Volts _____ Length of drop pipe <u>100</u> ft. capacity <u>650</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
Fine to coarse sand clay streaks				237	287	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne-Western Co., Inc. Business name _____ License No. _____ Address <u>Garden City, Kansas</u> Signed <u>[Signature]</u> Date <u>21 Oct 77</u> Authorized representative
Tan clay				287	300	
Fine to coarse sand				300	320	
Fine to coarse sand lots of clay streaks				320	360	
Black shale				360	380	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:				
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley						

T 24 S R 35 W E L 5 SW NE NW
1/4 1/4 1/4 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-3