

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 047 KEARNY 1/4 1/4 NW 1/4 22 T 24 S R 36 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 0.5 MILES NORTH OF LAKIN.

2 WATER WELL OWNER: WALLACE PEPPER  
 RR#, St. Address, Box #: N. HIWAY 25 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: LAKIN, KS 67860- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:  
 4 DEPTH OF COMPLETED WELL 210 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 26 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 26 ft. below land surface measured on mo/day/yr 02/28/92  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 50 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 9.875 in. to 220 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 210 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT  
 SCREEN PERFORATED INTERVALS: From 140 ft. to 160 ft., From 0 ft. to 0 ft.  
 From 170 ft. to 210 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 210 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	28	01 CLAY			
28	45	02 SILT 06 VERY FN SAND			
45	59	01 CLAY			
59	80	05 SAND 13 FINE GRAVEL 01 CLAY			
80	90	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
90	110	04 SANDY CLAY 07 FINE SAND			
110	125	05 SAND			
125	138	05 SAND 13 FINE GRAVEL			
138	165	05 SAND 14 MED GRAVEL 28 ROCK			
165	171	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/28/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/21/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) Douglas A. Henkle

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:      | Fraction                      | Section Number      | Township Number      | Range Number  
COUNTY: 047 KEARNY            |      1/4            1/4 NW      1/4      | 22                      | T 24            S            | R 36      W

2 WATER WELL OWNER:            WALLACE PEPPER  
RR#, St. Address, Box # :    N. HIWAY 25                      Board of Agriculture, Division of Water Resources  
  
City, State, ZIP code    :    LAKIN, KS      67860-                      Application Number:

FROM	TO	LITHOLOGIC LOG
171	185	07 FINE SAND 08 MEDIUM SAND
185	210	19 SHALE 23 SANDSTONE
210	216	19 SHALE
216	220	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/28/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145      This Water Well Record was completed on (mo/day/yr) 05/21/92 under the business name of HENKLE DRILLING & SUPPLY      by (signature) *Douglas A. Henkle*