

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 047 KEARNY SW 1/4 NE 1/4 NW 1/4 32 T 24 S R 36 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM LAKIN; APPX 1 3/4 MILES WEST

2 WATER WELL OWNER: MARCEL SIERSEMA  
 RR#, St. Address, Box #: RT 1 BOX 269 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: DEERFIELD, KS 67838-9556 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	W	NW X	NE				
M					E		
i							
l							
e		SW	SE				
\							/

4 DEPTH OF COMPLETED WELL 206 BLEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 76 ft. below land surface measured on mo/day/yr 07/26/05  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 11 in. to 206 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 6 in. to 206 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 4 lbs/ft. Wall thickness or gauge No. .316  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 166 ft. to 186 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 206 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	12	04 SANDY CLAY			
12	24	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
24	46	04 SANDY CLAY			
46	70	05 SAND 13 FINE GRAVEL			
70	80	04 SANDY CLAY 20 LIMESTONE 05 SAND			
80	103	07 FINE SAND 08 MEDIUM SAND			
103	126	04 SANDY CLAY 20 LIMESTONE			
126	155	31 CALICHE			
155	163	31 CALICHE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/03/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/09/05 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 047 KEARNY	Fraction SW 1/4 NE 1/4 NW 1/4	Section Number 32	Township Number T 24 S	Range Number R 36 W
---	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: MARCEL SIERSEMA  
RR#, St. Address, Box # : RT 1 BOX 269  
City, State, ZIP code : DEERFIELD, KS 67838-9556  
Board of Agriculture, Division of Water Resources  
Application Number: |

FROM	TO	LITHOLOGIC LOG
163	186	23 SANDSTONE
186	206	31 CALICHE
206	220	31 CALICHE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/03/05 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/09/05  
under the business name of HENKLE DRILLING & SUPPLY by (signature) 