

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 047 KEARNY NE 1/4 NW 1/4 NE 1/4 29 T 24 S R 36 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM LAKIN; APPX 2 MILES WEST

2 WATER WELL OWNER: COLORADO INTERSTATE GAS  
 RR#, St. Address, Box #: PO BOX 30699 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: AMARILLO, TX 79120-3069 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

/ \			X		
1	--- NW ---	---	NE ---	---	---
M i l e	W	---	---	E	---
\ /	---	SW ---	---	SE ---	---

4 DEPTH OF COMPLETED WELL 90 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 0 ft. below land surface measured on mo/day/yr  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 7 7/8 in. to 90 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 10 MONITORING

Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: OTR CASING JNT - CERTILON  
 Blank casing diameter 4 in. to 90 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 2 lbs/ft. Wall thickness or gauge No. .237  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 80 ft. to 90 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 75 ft. to 90 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 75 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT 28 ROCK			
2	35	04 SANDY CLAY			
35	43	05 SAND 13 FINE GRAVEL			
43	49	04 SANDY CLAY			
49	64	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
64	68	04 SANDY CLAY			
68	81	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
81	87	04 SANDY CLAY			
87	90	05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/16/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/19/05 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Richman*