

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: HAMILTON NW 1/4 NE 1/4 SE 1/4 11 T 24 S R 41 W

Distance and direction from nearest town or city street address of well if located within city?
 SYRACUSE - 1 M W. ON HIGHWAY 50 CROSS R.R. 1/4W, 1/4S & 1/4W

2 WATER WELL OWNER: HERNDON, LETHA Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: P.O. BOX 7 Application Number:
 City, State, ZIP code: SYRACUSE, KS 67878-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	NW	NE	E
H i l e	W	X	SE
	SW	SE	

4 DEPTH OF COMPLETED WELL 395 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 178 ft. below land surface measured on mo/day/yr 01/23/98
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 35 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 in. to 395 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 395 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 270 ft. to 330 ft., From 0 ft. to 0 ft.
 From 370 ft. to 390 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 160 ft. to 395 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 160 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? NORTH How many feet? 25

FROM:	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL FINE SAND COARSE SAND			
20	55	SAND COARSE SAND GRAVEL			
55	120	BLUE SHALE			
120	200	BLUE SHALE SANDSTONE IN LAYERS			
200	360	SANDSTONE			
360	380	GRAY CLAY SANDSTONE			
380	400	SANDSTONE CLAY ROCK LAYERS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/23/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 02/10/98 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Quaid Crist*