

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: HAMILTON SE 1/4 SE 1/4 SE 1/4 11 T 24 S R 42 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM SYRACUSE, KS - 10 W. WEST AND 2 W SOUTH ON RIVER ROAD

2 WATER WELL OWNER: TRIPLE T FARMS
 RR#, St. Address, Box #: BOX 69 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: LAKIN, KS 67860- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 285 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 71 ft. below land surface measured on no/day/yr 05/05/93
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 40 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 285 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLOUED
 Blank casing diameter 5 in. to 285 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 260 ft. to 280 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 From 25 ft. to 285 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? NORTHEAST How many feet? 20

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL FINE - MED SAND			
20	80	MED-COARSE SAND GRAVEL VERY LOOSE			
80	100	CLAY ROCK LAYERS SAND ROCK LAYER			
100	120	SANDSTONE ROCK LAYERS			
120	160	ROCK LAYERS SANDSTONE			
160	180	SANDSTONE THIN ROCK LAYER			
180	200	SANDSTONE IN LAYERS GRAY CLAY			
200	210	GRAY CLAY SANDSTONE			
210	240	SANDSTONE			
240	250	SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 05/05/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 06/23/93 under the business name of JOB'S WELL SERVICE, INC. by (signature)

(Continued) WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: HAMILTON SE 1/4 SE 1/4 SE 1/4 11 T 24 S R 42 W

2 WATER WELL OWNER: TRIPLE T FARMS
 RR#, St. Address, Box #: BOX 69 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: LAKIN, KS 67860- Application Number:

FROM	TO	LITHOLOGIC LOG
250	280	SANDSTONE VERY LOOSE