

~~24-43-10~~ ~~and~~ ~~Sample~~ Driller's log of test hole ~~244310~~ drilled

(Well No.)

by C. K. Minter Drilling Co. for KGS

in Hamilton County, 0.2 miles south of NE $\frac{1}{4}$ of sec. 10, to 24 S., R. 43 W.
(Location)

12-20-67; depth to water, _____ feet;
(Date)

altitude of land surface 3376 _____ feet.

	Thickness, feet	Depth, feet
Dune sand, fine to medium, silty	19	19
Clay, silty, tan, very calcareous	8	27
Sand, very fine to medium, very loose	7	34
Sand, medium to medium gravel, very loose	10	44
Sand, coarse to coarse gravel, loose, with few cemented layers; calcareous; contains limestone, sandstone, and granite cobbles	44	88
Gravel, medium to coarse and cobbles, tightly cemented, calcareous	6	94
Shale, sandy, light gray to dark gray, hard	7	101
Total Depth		101'

3376
94
 3282