

1 LOCATION OF WATER WELL:		Fraction NW 1/4 NW 1/4 NW 1/4		Section Number 22	Township Number T 24 S	Range Number R 5 EW
County: Reno Distance and direction from nearest town or city street address of well if located within city? 1 mi N of Yoder						
2 WATER WELL OWNER:		Yoder Mennonite Church			Board of Agriculture, Division of Water Resources	
RR#, St. Address, Box # :		Rt 2			Application Number:	
City, State, ZIP Code :		Haven, KS 67543				
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 78 ft. ELEVATION:				
		Depth(s) Groundwater Encountered 1. 49 ft. 2. 11-13-84 ft. 3. 25 ft.				
		WELL'S STATIC WATER LEVEL 49 ft. below land surface measured on mo/day/yr 11-13-84				
		Pump test data: Well water was 52 ft. after 2 hours pumping 25 gpm				
		Est. Yield 50 gpm: Well water was ft. after hours pumping gpm				
		Bore Hole Diameter 10 in. to 80 ft., and in. to ft.				
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well				
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)				
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well				
		Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted				
		Water Well Disinfected? Yes X No				
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued X Clamped				
1 Steel 3 RMP (SR)		Welded				
2 PVC 4 ABS		Threaded				
Blank casing diameter 6 in. to 6.8 ft., Dia		in. to ft., Dia				
Casing height above land surface 12 in., weight 3.35 lbs./ft.		Wall thickness or gauge No. 160				
TYPE OF SCREEN OR PERFORATION MATERIAL:		10 Asbestos-cement				
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR)		11 Other (specify)				
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS		12 None used (open hole)				
SCREEN OR PERFORATION OPENINGS ARE:		11 None (open hole)				
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut		9 Drilled holes				
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)						
SCREEN-PERFORATED INTERVALS: From 68 ft. to 78 ft.		ft. to ft.				
GRAVEL PACK INTERVALS: From 60 ft. to 80 ft.		ft. to ft.				
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other						
Grout Intervals: From 4 ft. to 14 ft.		ft. to ft.				
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well				
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well		12 Fertilizer storage 16 Other (specify below)				
2 Sewer lines 5 Cess pool 8 Sewage lagoon 13 Insecticide storage						
3 Watertight sewer lines 6 Seepage pit 9 Feedyard						
Direction from well? S		How many feet? 70				
FROM TO LITHOLOGIC LOG		FROM TO LITHOLOGIC LOG				
0 42 Br Clay						
42 65 F-C Sand - sm Gravel						
65 69 Sand - WT Rock						
69 72 C Sand						
72 74 Lt Br Clay						
74 79 C Sand						
79 80 Gr Clay						
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 11-13-84 and this record is true to the best of my knowledge and belief. Kansas						
Water Well Contractor's License No. 449 This Water Well Record was completed on (mo/day/yr) 2-18-85						
under the business name of Miller Drilling by (signature) Egan Miller						
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.						